PRELIMINARY/FINAL LAND DEVELOPMENT PLANS

FOR **IPASS HEALTH REHABILITATION HOSPITAL OF NORRISTOWN** 2660 AUDUBON ROAD, NORRISTOWN, PA 19403

	Wetherills
200-	APPLE VALLEY LN
	nerills THR
	150)
I'kill River Washington	
Memorial Chapel-Cem	

	Sheet List Table
Sheet Number	Sheet Title
C-00 C-01	COVER SHEET
C-01	GENERAL NOTES EXISTING CONDITIONS AND DEMOLITION PLAN
C-02B	OVERALL SITE PLAN
C-04A	SITE PLAN WEST
C-04B	SITE PLAN EAST
C-04C	SITE PLAN DETAILS
C-04D	SITE PLAN DETAILS
C-04E	AIRGAS CONSTRUCTION DETAILS
C-05A	TRUCK ROUTING PLAN
C-05B	TRUCK ROUTING PLAN
C-05C	FIRE TRUCK ROUTING PLAN
C-05D	GARBAGE TRUCK ROUTING PLAN
C-06	EROSION AND SEDIMENT CONTROL PLAN
C-06A	EROSION AND SEDIMENT CONTROL PLAN WEST
C-06B	EROSION AND SEDIMENT CONTROL PLAN EAST
C-06C	EROSION AND SEDIMENT CONTROL PLAN SOUTH
C-06D	EROSION AND SEDIMENT CONTROL NOTES
C-06E C-06F	EROSION AND SEDIMENT CONTROL DETAILS EROSION AND SEDIMENT CONTROL DETAILS
C-06F	OVERALL POST CONSTRUCTION STORMWATER MANAGEMENT PLA
C-07A	POST CONSTRUCTION STORMWATER MANAGEMENT PLAN WEST
C-07B	POST CONSTRUCTION STORMWATER MANAGEMENT PLAN EAST
C-07C	POST CONSTRUCTION STORMWATER MANAGEMENT PLAN SOUTH
C-07D	POST CONSTRUCTION STORMWATER MANAGEMENT PROFILES
C-07E	POST CONSTRUCTION STORMWATER MANAGEMENT PROFILES
C-07F	POST CONSTRUCTION STORMWATER MANAGMENT NOTES
C-07G	POST CONSTRUCTION STORMWATER MANAGEMENT DETAILS
C-07H	POST CONSTRUCTION STORMWATER MANAGEMENT DETAILS
C-07I	POST CONSTRUCTION STORMWATER MANAGEMENT DETAILS
C-08	OVERALL GRADING PLAN
C-08A	GRADING PLAN WEST
C-08B	GRADING PLAN EAST
C-08C	GRADING PLAN SOUTH
C-08D	SITE SECTIONS
C-08E	DRIVEWAY PROFILE
C-09	
C-09A	
C-09B C-09C	UTILITY PLAN EAST UTILITY PROFILES
C-09C	UTILITY DETAILS
C-09D	UTILITY DETAILS
C-10	SIGNAGE AND PAVEMENT MARKING
C-10A	SIGNAGE AND PAVEMENT MARKING WEST
C-10B	SIGNAGE AND PAVEMENT MARKING EAST
C-10C	SIGNAGE AND PAVEMENT MARKING ENLARGEMENTS
C-10D	SIGNAGE AND PAVEMENT MARKING ENLARGEMENTS
L-01	LANDSCAPE PLAN
L-01A	LANDSCAPE PLAN WEST
L-01B	LANDSCAPE PLAN EAST
L-01C	LANDSCAPE DETAILS
LAND USE	DEVELOPMENT DATA
TOTAL AREA:	10.1 AC.
PARCEL ID:	430000823007
PRESENT ZONING:	LIMITED INDUSTRIAL (LI)
ABUTTING ZONING:	EAST: LIMITED INDUSTRIAL (LI) NORTH: INDUSTRIAL PARK (IP)
	SOUTH: MOBILE HOME PARK (MHP)
	±8.02 AC.
PROJECT AREA:	10.02 AC.


LIMITED INDUSTRIAL (LI) FUTURE LAND USE:

PROJECT LOCATION LOCATED AT 2660 AUDUBON ROAD, NORRISTOWN, PENNSYLVANIA, 19403

BUILDING HEIGHT PROPOSED BUILDING HEIGHT IS <90 FT. (REFER TO ARCHITECTURAL PLANS)

50-BED REHABILITATION HOSPITAL WITH 30-BED FUTURE EXPANSION: TOTAL EMPLOYEE PARKING REQUIRED = 60 SPACES TOTAL VISITOR PARKING REQUIRED = 40 SPACES TOTAL HANDICAP PARKING REQUIRED = 6 SPACES TOTAL PARKING REQUIRED = 106 SPACES TOTAL EMPLOYEE PARKING PROVIDED = 82 SPACES TOTAL VISITOR PARKING PROVIDED = 55 SPACES HANDICAP PARKING PROVIDED = 16 SPACES TOTAL PARKING PROVIDED = 153 SPACES

SEPTEMBER 2023



USGS MAP VALLEY FORGE QUADRANGLE DATED 2019 (SCALE 1" = 1000')

SITE MAP IMAGERY FROM NEAR MAP ACCESSED APRIL 25, 2023. (SCALE 1" = 500')

APPLICANT | OWNER | ENGINEER OF RECORD

APPLICANT \ OWNER:

ENCOMPASS HEALTH PENNSYLVANIA REAL ESTATE, LLC, A DELAWARE LIMITED LIABILITY COMPANY 9001 LIBERTY PARKWAY BIRMINGHAM, AL 35242 205-970-5586 CONTACT: TAYLOR BRADLEY

ENGINEER OF RECORD:

KIMLEY-HORN AND ASSOCIATES, INC. 750 HOLIDAY DRIVE, SUITE 750 PITTSBURGH, PA 15220 412-218-2210 CONTACT: BILL MOLDOVAN, RLA

UTILITY CONTACTS

LOWER PROVIDENCE TOWNSHIP SEWER AUTHORITY

WATER:

AUDUBON WATER COMPANY 2650 EISENHOWER AVENUE NORRISTOWN, PA 19403 610-630-1200 CONTACT: JH RUSSELL

GAS:

PECO ENERGY COMPANY 300 W. WASHINGTON STREET NORRISTOWN, PA 19401 610-239-8008 CONTACT:

ELECTRIC:

610-539-6161

SEWAGE:

20 PARKLANE DRIVE


EAGLEVILLE, PA 19403

PECO 680 RIDGE PIKE PLYMOUTH MEETING, PA 19462 800-494-4000 CONTACT:

CONTACT: ALAN M. RUBENDALL

TELECOMM:

VERIZON ONE VERIZON WAY BASKING RIDGE, NJ 07920 215-789-7728 CONTACT: DAVE STINSON



MAXIMUM LOT COVER MINIMUM SITE SIZ



ADDRESS			2660 AUDUBON ROAD
G DISTRIC	Г		L1 - LIMITED INDUSTRIAL
ING USE		Μ	EDICAL/SURGICAL CENTER
DNI	NG INF	ORM	IATION
	REQU	JIRED	PROVIDED
EA	1 ACRE		10.1 ACRES
TH	150 FEET		>150 FEET
TBACK	60 F	EET	87.8 FEET
BACK	25 F	EET	78.8 FEET
BACK	30 F	EET	103.4 FEET
IEIGHT	90 F	EET	VARIES < 90 FEET
RAGE	50)%	42%
ZE	10 AC	CRES	10.1 ACRES

	Greshan Smith	1
	GreshamSmith.com 2222 Arlington Avenue	
VN	Suite 202 Birmingham, AL 352	
	Kimley »Ho	rn
	STRUCTURAL CIVIL GEOT	RS, INC.
	88 550	e
	Encomp Health	ass
	ENCOMPASS HEALTH REHABILITATION HOSPITAL OF NORRISTOWN	PRELIMINARY/FINAL LAND DEVELOPMENT 2660 Audubon Road, Norristown, PA 19403
AD RIAL ENTER VIDED ACRES D FEET FEET FEET FEET 4 FEET 4 FEET 4 FEET 2% ACRES	Revision No. Date Desc I I I <tr< th=""><th></th></tr<>	
PENNSYLVANIA LAW REQUIRES 3 WORKING DAYS NOTICE FOR CONSTRUCTION PHASE AND 10 WORKING DAYS IN DESIGN STAGE - STOP CALL	COVER SHEE	
PRELIMINARY NOT FOR CONSTRUCTION	112642001 08/30/2023	,

This Line is 3 Inches When Printed Full Size

CON	STRUCTION STANDARDS	DEM	IOLITION / LAND DISTURBANCE NOTE
1.	ALL CONSTRUCTION METHODS AND MATERIALS SHALL CONFORM WITH THESE DRAWINGS, PROJECT SPECIFICATIONS, WITH ALL CURRENT APPLICABLE CODES, AND, UNLESS OTHERWISE SPECIFIED, WITH THE LATEST REVISIONS OF THE FOLLOWING REFERENCE DOCUMENTS:	1.	
	 PENNSYLVANIA DEPARTMENT OF TRANSPORTATION (PENNDOT) LATEST RC STANDARDS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD) DENNSYLVANIA DEPARTMENT OF TRANSPORTATION (PENNDOT) DATA TRAFFIC CONTROL DIACDAMS 		B. INSTALLING THE REQUIRED S MEASURES PRIOR TO SITE DIST
	 C. PENNSYLVANIA DEPARTMENT OF TRANSPORTATION (PENNDOT) PATA TRAFFIC CONTROL DIAGRAMS. D. PENNSYLVANIA EROSION AND SEDIMENT CONTROL MANUAL 		C. LOCATING (VERTICALLY AND LIMITED TO GAS, WATER, ELECT
			CABLE, ETC. WITHIN THE LIMITS THE REQUIREMENTS OF THE AP UNDERGROUND UTILITIES.
1.	ALL CONSTRUCTION SHALL CONFORM WITH APPLICABLE STATE (INCLUDING PENNDOT) AND LOCAL CONSTRUCTION STANDARDS AS IDENTIFIED IN THESE PLANS. THE CONTRACTOR SHALL OBTAIN ALL APPLICABLE PERMITS AND LICENSES AND MAINTAIN COPIES OF THEM ON-SITE AT ALL TIMES DURING CONSTRUCTION. THE CONTRACTOR SHALL MAINTAIN A SET OF CONSTRUCTION DOCUMENTS, SPECIFICATIONS, AND EROSION AND SEDIMENTATION CONTROL PLANS ON-SITE AT ALL TIMES DURING CONSTRUCTION.		D. FAMILIARIZING THEMSELVES RESPONSIBLE FOR ALL COORDI PROJECT. THE CONTRACTOR SI EXISTING UTILITIES AND SERVIC JURISDICTION AND UTILITY COM DEMOLITION OPERATIONS THAT PRESERVED AND PROTECTED.
	SPECIFICATIONS ASSOCIATED WITH THE PROJECT WORK SCOPE PRIOR TO THE INITIATION OF CONSTRUCTION. SHOULD THE CONTRACTOR FIND A CONFLICT WITH THE DOCUMENTS RELATIVE TO THE SPECIFICATIONS OR THE RELATIVE CODES, IT IS THE CONTRACTOR'S RESPONSIBILITY TO NOTIFY THE PROJECT ENGINEER OF RECORD IN WRITING PRIOR TO THE START OF CONSTRUCTION. FAILURE BY THE CONTRACTOR TO NOTIFY THE PROJECT ENGINEER SHALL CONSTITUTE ACCEPTANCE OF FULL		E. COORDINATION WITH UTILITY WORKING "OFF-PEAK" HOURS O THE AFFECTED PARTIES.
	RESPONSIBILITY BY THE CONTRACTOR TO COMPLETE THE SCOPE OF WORK AS DEFINED BY THE DRAWINGS AND IN FULL COMPLIANCE WITH LOCAL REGULATIONS AND CODES.	2.	NEITHER KIMLEY-HORN & ASSOCIA SUPERVISION. CONTRACTOR IS TO MANNER, FOLLLOWING ALL OSHA F
3.	ALL PAINT STRIPING, PAVEMENT MARKINGS, AND SIGNAGE SHALL CONFORM TO THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES," MOST CURRENT REVISION OR AS OTHERWISE SPECIFIED. ALL REFERENCED SIGN STANDARDS ARE TAKEN FROM THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES". ALL NEW SIGNS SHALL BE MOUNTED ON GALVANIZED POSTS AND IN ACCORDANCE WITH STATE AND LOCAL REGULATIONS	3.	THE CONTRACTOR SHALL PROVIDE MOVEMENT, SETTLEMENT, OR COL THAT ARE REMAINING ON OR OFF REPAIRS OF DAMAGE TO ALL ITEM
4.	ANY DAMAGE OCCURRING TO THE EXISTING SITE INFRASTRUCTURE ON THIS OR THE ADJACENT SITE DURING THE CONSTRUCTION OPERATIONS AND/OR MOBILIZATION, SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. ALL EXISTING DAMAGED ITEMS INCLUDING CONCRETE AND/OR PAVEMENT SECTIONS SHALL BE RESTORED TO THEIR ORIGINAL CONDITIONS PRIOR TO PROJECT COMPLETION AT	4.	IN THE ABSENCE OF SPECIFICATIO DEMOLITION AND REMOVAL OF ALL LIMITS OF DISTURBANCE WITH DIR
5.	THE EXPENSE OF THE CONTRACTOR. THE CONTRACTOR SHALL BE RESPONSIBLE FOR REPLACING WITH MATCHING MATERIALS ANY PAVEMENT, DRIVEWAYS, WALKS, CURBS, ETC. THAT MUST BE CUT OR THAT ARE DAMAGED DURING CONSTRUCTION INSIDE AND OUTSIDE OF THE LIMITS OF CONSTRUCTION.	5.	CONTRACTOR SHALL PROVIDE TRA CONFORMANCE WITH: THE "MANUA LOCAL REGULATIONS WHEN DEMO - OF - WAY.
6.	ANY AND ALL UTILITIES AND/OR OBSTRUCTIONS (POWER POLES, TELEPHONE PEDESTALS, GUY WIRES, WATER METERS, ETC.) THAT ARE REQUIRED TO BE RELOCATED OR ADJUSTED DUE TO CONSTRUCTION SHALL BE DONE SO AT THE OWNERS/DEVELOPERS EXPENSE.	6.	CONDUCT DEMOLITION ACTIVITIES STREETS, SIDEWALKS, WALKWAYS BE RECEIVED FROM THE APPROPR
7.	THE CONTRACTOR IS RESPONSIBLE TO REMOVE ALL THE REMOVED/DEMOLISHED MATERIAL FROM THE PROJECT SITE AND DISPOSE OF SAME IN A LEGAL MANNER.	7.	USE DUST CONTROL MEASURES TO IN ACCORDANCE WITH FEDERAL, S COMPLETE, ADJACENT STRUCTUR
8.	TYING TO EXISTING PAVEMENT: EXISTING PAVEMENT SHALL BE NEATLY SAW CUT TO A STRAIGHT LINE AND ALL PAVING ON THE NEW PAVEMENT SIDE OF THE CUT SHALL BE COMPLETELY REMOVED AND REPLACED WITH SPECIFIED MATERIALS. THE CUT LINE SHALL BE FULL DEPTH AND COATED WITH A	2	CAUSED BY THE DEMOLITION OPER ADJACENT AREAS TO THEIR "PRE-I
	REPLACED WITH SPECIFIED MATERIALS. THE CUT LINE SHALL BE FULL-DEPTH AND COATED WITH A TACK COAT TO FURNISH A BOND BETWEEN THE EXISTING SURFACE COURSE AND THE NEW SURFACE COURSE.	8.	CONTRACTOR IS RESPONSIBLE TO SUCH A MANNER AS TO PREVENT
9.	THESE PLANS ARE BASED ON INFORMATION PROVIDED TO KIMLEY-HORN & ASSOCIATES, INC. AT THE TIME OF PLAN PREPARATION. CONTRACTOR SHALL FIELD VERIFY EXISTING CONDITIONS PRIOR TO CONSTRUCTION AND NOTIFY KIMLEY-HORN & ASSOCIATES, INC. IF ACTUAL SITE CONDITIONS DIFFER FROM THOSE SHOWN ON THE PLAN, OR IF THE PROPOSED WORK WOULD BE INHIBITED BY ANY OTHER SITE FEATURES.	9.	THIS DEMOLITION PLAN IS INTENDE REMOVED. IT IS NOT INTENDED TO ARE TO BE IN ACCORDANCE WITH CONTRACTOR SHALL BE RESPONS PROVIDE A SAFE WORK SITE.
10.	ANY DISCREPANCIES ON THE DRAWINGS SHALL BE IMMEDIATELY BROUGHT TO THE ATTENTION OF THE ARCHITECT AND ENGINEER BEFORE COMMENCING WORK. NO FIELD CHANGES OR DEVIATIONS FROM DESIGN ARE TO BE MADE WITHOUT PRIOR APPROVAL OF THE OWNER AND NOTIFICATION TO THE ENGINEER. NO CONSIDERATION WILL BE GIVEN TO CHANGE ORDERS FOR WHICH THE OWNER AND	10. 11.	DEBRIS SHALL NOT BE BURIED ON WASTE) SHALL BE DISPOSED OF IN APPLICABLE CODES. ALL ORGANICS AND TOPSOIL SHAL
11.	ENGINEER WERE NOT CONTACTED PRIOR TO CONSTRUCTION OF THE AFFECTED ITEM. ALL DIMENSIONS SHOWN ON THE PLANS SHALL BE FIELD VERIFIED BY THE CONTRACTOR PRIOR TO		TOPSOIL FOR REUSE, IF NECESSAI SEDIMENTATION CONTROL PLAN.
	CONSTRUCTION. CONTRACTOR SHALL NOTIFY ENGINEER AND OWNER IN WRITING IF ANY DISCREPANCIES EXIST PRIOR TO PROCEEDING WITH CONSTRUCTION. NO EXTRA COMPENSATION SHALL BE PAID TO THE CONTRACTOR FOR WORK HAVING TO BE REDONE DUE TO DIMENSIONS OR		REMOVE VEGETATION, GRASS, & R PAVEMENTS.
12.	GRADES SHOWN INCORRECTLY ON THESE PLANS IF SUCH NOTIFICATION HAS NOT BEEN GIVEN. CONTRACTOR SHALL REFER TO THE ARCHITECTURAL/BUILDING PLANS FOR EXACT LOCATIONS AND DIMENSIONS OF ENTRY/EXIT POINTS, ELEVATIONS, PRECISE BUILDING DIMENSIONS, EXACT BUILDING	13.	RELOCATION FROM DAMAGE DURI
13.	UTILITY LOCATIONS. IF THE CONTRACTOR DEVIATES FROM THE PLANS AND SPECIFICATIONS, INCLUDING THE NOTES	14.	ANY STREET SIGNS DAMAGED OR REPLACED IN KIND OR PER LOWER SAW CUT AND REMOVE ALL ASPHA
	CONTAINED THEREON, WITHOUT FIRST OBTAINING WRITTEN AUTHORIZATION FOR SUCH DEVIATIONS FROM THE OWNER AND ENGINEER, IT SHALL BE RESPONSIBLE FOR THE PAYMENT OF ALL COSTS TO CORRECT ANY WORK DONE, ALL FINES OR PENALTIES ASSESSED WITH RESPECT THERETO AND ALL	16.	
	COMPENSATORY OR PUNITIVE DAMAGES RESULTING THEREFROM. THE CONTRACTOR SHALL INDEMNIFY AND HOLD THE OWNER AND ENGINEER HARMLESS FROM ALL SUCH COSTS TO CORRECT ANY SUCH WORK AND FROM ALL SUCH FINES AND PENALTIES, COMPENSATION AND PUNITIVE DAMAGES	17.	
14.	AND COSTS OF ANY NATURE RESULTING THEREFROM. BRACING OF UTILITY POLES MAY BE REQUIRED BY UTILITY COMPANIES WHEN TRENCHING OR	18.	CONTRACTOR STAGING AREAS SH
	EXCAVATION IS IN CLOSE PROXIMITY TO THE POLES. THE COST OF BRACING POLES WILL BE BORNE BY THE CONTRACTOR. THERE IS NO SEPARATE PAY ITEM FOR THIS WORK. THE COST IS INCIDENTAL TO THE VARIOUS PAY ITEMS FOR INSTALLATION OF PIPE.	19.	LIMITS OF DEMOLITION INDICATED PAVEMENT, CONCRETE AND MISCE ACCORDANCE WITH STATE AND LC
15.	ALL EXISTING TRAFFIC AND STREET SIGNS DISTURBED SHALL BE REINSTALLED WHERE APPLICABLE BY THE CONTRACTOR.	20.	CONTRACTOR SHALL BE RESPONS CONSTRUCTION.
16.	UNLESS THE PLANS SPECIFICALLY DICTATE TO THE CONTRARY, ON-SITE AND OTHER DIRECTIONAL SIGNS SHALL BE LOCATED OUT OF THE PEDESTRIAN AND AUTOMOBILE ROUTES AND SHALL BE LOCATED BETWEEN THREE TO FIVE FEET BEHIND THE NEAREST BACK OF CURB. SIGN HEIGHT, LOCATION, AND STRUCTURE SHALL BE SUCH THAT THE SIGNS POSE NO THREAT TO PUBLIC SAFETY.		
17.	ALL DIMENSIONS ARE TO FACE OF CURB UNLESS OTHERWISE NOTED. ALL CURB RADII GIVEN TO THE FACE OF CURB. ALL CURB RADII TO BE 5' UNLESS OTHERWISE NOTED.		
18.	THE CONTRACTOR SHALL VERIFY DIMENSIONS AT JOBSITE.		
19.	CONTRACTOR SHALL INSTALL ACCESSIBLE RAMPS PER PENNDOT AND ADA STANDARDS AT ALL DRIVE AND BUILDING LOCATIONS AS REQUIRED.		
20.	CONTRACTOR IS RESPONSIBLE FOR THE INSTALLATION AND MAINTENANCE OF ALL EROSION CONTROL DEVICES SHOWN ON THE APPROVED PLANS FOR THE DURATION OF CONSTRUCTION OR UNTIL FINAL INSPECTION.		
21.	APPROVAL OF THIS PLAN IS NOT AN AUTHORIZATION TO GRADE ADJACENT PROPERTIES. WHEN FIELD CONDITIONS WARRANT OFF-SITE GRADING, PERMISSION MUST BE OBTAINED FROM THE AFFECTED PROPERTY OWNERS.		
22.	ALL WORK IN THE RIGHT-OF-WAY REQUIRES A RIGHT-OF-WAY PERMIT FROM MONTGOMERY COUNTY. CONTRACTOR SHALL SECURE ALL REQUIRED CONSTRUCTION PERMITS.		
23.	CONTRACTOR SHALL BE RESPONSIBLE FOR ALL RELOCATIONS, (UNLESS OTHERWISE NOTED ON PLANS) INCLUDING BUT NOT LIMITED TO, ALL UTILITIES, STORM DRAINAGE, SIGNS, TRAFFIC SIGNALS & POLES, ETC. AS REQUIRED. ALL WORK SHALL BE IN ACCORDANCE WITH GOVERNING AUTHORITIES REQUIREMENTS AND PROJECT SITE WORK SPECIFICATIONS AND SHALL BE APPROVED BY SUCH. ALL COST SHALL BE INCLUDED IN BASE BID.		

TES

LITION CONTRACTOR IS RESPONSIBLE FOR/TO: F ALL APPLICABLE PERMITS AND APPROVALS ARE MAINTAINED ON SITE

) SOIL EROSION AND SEDIMENT CONTROL AND/OR TREE PROTECTION STURBANCE.

ID HORIZONTALLY) ALL UTILITIES AND SERVICES, INCLUDING, BUT NOT CTRIC, SANITARY AND STORM SEWER, TELEPHONE, CABLE, FIBER OPTIC TS OF DISTURBANCE. THE CONTRACTOR SHALL USE AND COMPLY WITH APPLICABLE UTILITY NOTIFICATION SYSTEM TO LOCATE ALL THE

ES WITH THE APPLICABLE UTILITY SERVICE PROVIDER AND IS DINATION REGARDING UTILITY DEMOLITION REQUIRED FOR THE SHALL PROVIDE THE OWNER WRITTEN NOTIFICATION THAT THE /ICES HAVE BEEN TERMINATED AND ABANDONED IN ACCORDANCE WITH OMPANY REQUIREMENTS. ALL PRIMARY UTILITIES DISCOVERED DURING AT SERVE ACTIVITIES OTHER THAN THE SITE SHALL BE PROPERLY

TY COMPANIES & ADJACENT LANDOWNERS/BUSINESSES REGARDING OR ON WEEKENDS AS MAY BE REOUIRED TO MINIMIZE THE IMPACT ON

CIATES, INC. NOR THE OWNER IS RESPONSIBLE FOR JOB SITE SAFETY OR TO PROCEED WITH THE DEMOLITION IN A SYSTEMATIC AND SAFE A REQUIREMENTS, TO ENSURE PUBLIC AND CONTRACTOR SAFETY.

IDE ALL THE "MEANS AND METHODS" NECESSARY TO PREVENT OLLAPSE OF EXISTING STRUCTURES, AND ANY OTHER IMPROVEMENTS F SITE. THE DEMOLITION CONTRACTOR IS RESPONSIBLE FOR ALL MS THAT ARE TO REMAIN AS A RESULT OF HIS ACTIVITIES.

IONS, THE CONTRACTOR SHALL PERFORM EARTH MOVEMENT ACTIVITIES, ALL FOUNDATION WALLS, FOOTINGS, AND OTHER MATERIALS WITHIN THE IRECTION BY OWNER'S STRUCTURAL OR GEOTECHNICAL ENGINEER.

RAFFIC CONTROL AND GENERALLY ACCEPTED SAFE PRACTICES IN IUAL ON UNIFORM TRAFFIC CONTROL," AS WELL AS FEDERAL, STATE, AND MOLITION RELATED ACTIVITIES IMPACT ROADWAYS OR ROADWAY RIGHTS

ES IN SUCH A MANNER TO ENSURE MINIMUM INTERFERENCE WITH ROADS, YS, AND OTHER ADJACENT FACILITIES. STREET CLOSURE PERMITS MUST PRIATE GOVERNMENTAL AUTHORITY.

TO LIMIT AIRBORNE DUST AND DIRT RISING AND SCATTERING IN THE AIR , STATE, AND/OR LOCAL STANDARDS. AFTER THE DEMOLITION IS JRES AND IMPROVEMENTS SHALL BE CLEANED OF ALL DUST AND DEBRIS PERATIONS. THE CONTRACTOR IS RESPONSIBLE FOR RETURNING ALL E-DEMOLITION" CONDITION.

TO SAFEGUARD SITE AS NECESSARY TO PERFORM THE DEMOLITION IN T THE ENTRY OF UNAUTHORIZED PERSONS AT ANY TIME.

IDED TO IDENTIFY THOSE EXISTING ITEMS/CONDITIONS WHICH ARE TO BE TO PROVIDE DIRECTION OTHER THAN THAT ALL METHODS AND MEANS H STATE, FEDERAL, LOCAL, AND JURISDICTIONAL REQUIREMENTS. THE NSIBLE FOR ALL OSHA AND OTHER SAFETY PRECAUTIONS NECESSARY TO

IN THE SUBJECT SITE. ALL DEMOLITION WASTES AND DEBRIS (SOLID IN ACCORDANCE WITH ALL LOCAL, STATE, AND FEDERAL LAWS AND

ALL BE REMOVED FROM THE ENTIRE LIMITS OF DISTURBANCE. STOCKPILE SARY, IN ACCORDANCE WITH THE APPROVED EROSION AND

ROOTMAT IN AREAS TO RECEIVE NEW ASPHALT AND CONCRETE

EXISTING PLANT MATERIAL NOT DESIGNATED FOR REMOVAL OR RING CONSTRUCTION.

R TEMPORARILY REMOVED DURING CONSTRUCTION ARE TO BE ER PROVIDENCE TOWNSHIP AND PENNSYLVANIA DOT.

HALT AND CONCRETE TO LIMITS REQUIRED FOR NEW WORK.

DIATELY REPORT TO THE OWNER ANY UNFORESEEN OR ADVERSE NG DEMOLITION OPERATIONS.

SURROUNDING PUBLIC ROADWAYS AND DRAINAGE SYSTEMS FREE FROM DEBRIS AT ALL TIMES.

SHALL BE LIMITED TO THE PROPERTY BOUNDARY.

D ON PLAN ARE MINIMUM. CONTRACTOR SHALL REMOVE ASPHALT CELLANEOUS ITEMS AS NECESSARY TO FACILITATE CONSTRUCTION IN LOCAL REGULATIONS.

NSIBLE FOR THE REPAIR OF ANY ITEMS DAMAGED DURING

GRADING NOTES

- 1. SITE GRADING SHALL NOT PROCEED UNTIL EROSION CONTROL MEASURES HAVE BEEN INSTALLED AND APPROVED BY APPLICABLE AUTHORITY.
- 2. EXISTING AND PROPOSED GRADE CONTOUR INTERVALS SHOWN AT 2 FOOT. VERTICAL DA NAVD 88.
- 3. TOPOGRAPHIC INFORMATION IS TAKEN FROM A TOPOGRAPHIC SURVEY BY CONTROL POIN ASSOCIATES, INC. IF THE CONTRACTOR DOES NOT ACCEPT EXISTING TOPOGRAPHY AS S ON THE PLANS, WITHOUT EXCEPTION, THEN THE CONTRACTOR SHALL SUPPLY, AT THEIR EXPENSE, A TOPOGRAPHIC SURVEY BY A REGISTERED LAND SURVEYOR TO THE OWNER REVIEW.
- 4. ALL ELEVATIONS ARE IN REFERENCE TO THE BENCHMARK, AND THIS MUST BE VERIFIED A LOCATED BY THE GENERAL CONTRACTOR PRIOR TO GROUND BREAKING.
- 5. CONTRACTOR SHALL ENSURE POSITIVE DRAINAGE SO THAT RUNOFF WILL DRAIN BY GRAV FLOW ACROSS NEW PAVEMENT AREAS TO NEW OR EXISTING DRAINAGE INLETS OR SHEE FLOW OVERLAND. ENSURE POSITIVE DRAINAGE AWAY FROM THE BUILDING.
- 6. THE CONTRACTOR SHALL ADHERE TO ALL TERMS & CONDITIONS AS OUTLINED IN THE GENERAL/INDIVIDUAL NPDES PERMIT FOR STORMWATER DISCHARGE ASSOCIATED WITH CONSTRUCTION ACTIVITIES.
- 7. AFTER PLACEMENT OF SUBGRADE AND PRIOR TO PLACEMENT OF PAVEMENT, CONTRACT SHALL TEST AND OBSERVE PAVEMENT AREAS FOR EVIDENCE OF PONDING. ALL AREAS SI ADEQUATELY DRAIN TOWARDS THE INTENDED STRUCTURE TO CONVEY STORM RUNOFF. CONTRACTOR SHALL IMMEDIATELY NOTIFY OWNER AND ENGINEER IF ANY DISCREPANCIE DISCOVERED.
- 8. CONTRACTOR SHALL ADJUST AND/OR CUT EXISTING PAVEMENT AS NECESSARY TO ASSU SMOOTH FIT AND CONTINUOUS GRADE.
- 9. CONTRACTOR TO MATCH EXISTING GRADE AT PROJECT PROPERTY LINES AND LIMITS OF DISTURBANCE.
- 10. NO GRADED SLOPE SHALL EXCEED 2H:1V.
- 11. SLOPES WITHIN THE LIMITS OF THE HANDICAPPED PARKING AREAS SHALL NOT EXCEED 1 ANY DIRECTION. CROSSWALKS AND SIDEWALKS SHALL HAVE A MAXIMUM CROSS SLOPE C AND A MAXIMUM LONGITUDINAL SLOPE OF 5% IN DIRECTION OF TRAVEL. SLOPES IN HAND RAMPS SHALL BE BUILT IN CONFORMANCE WITH THE LATEST ADA CRITERIA AND LOCAL DE STANDARDS.SIDEWALK/SHOULDER GRADE AND CROSS SLOPE IS TO A MAXIMUM OF $\frac{1}{4}$ " PEF (2%, PER ADA).

DRAINAGE / STORMWATER NOTES

- 1. ALL EXISTING AND PROPOSED STORM SEWER PIPES, MANHOLES, AND CURB INLETS SHALI CLEANED OF DEBRIS AND ERODED MATERIALS AT THE LAST STAGES OF CONSTRUCTION.
- 2. CONTRACTOR SHALL VERIFY LOCATION AND DEPTH OF EXISTING STORMWATER STRUCTU CONTRACTOR SHALL NOTIFY ENGINEER IF EXISTING CONDITIONS DO NOT MATCH INFORM ON PLANS.
- 3. ALL INLETS AND MANHOLES SHALL MEET PENNDOT RC STANDARDS, LATEST EDITION.
- 4. GENERAL CONTRACTOR SHALL NOTIFY ALL UTILITY COMPANIES HAVING UNDERGROUND UTILITIES ON SITE OR IN RIGHT-OF-WAY PRIOR TO EXCAVATION. CONTRACTOR SHALL CON UTILITY LOCATING COMPANY AND LOCATE ALL UTILITIES PRIOR TO GRADING START.
- THE CONTRACTOR SHALL ADHERE TO ALL TERMS & CONDITIONS AS OUTLINED IN THE GENERAL/INDIVIDUAL NPDES PERMIT FOR STORMWATER DISCHARGE ASSOCIATED WITH CONSTRUCTION ACTIVITIES.
- 6. ALL DRAINAGE STRUCTURES AND STORM SEWER PIPES SHALL MEET HEAVY DUTY TRAFFI (H20) LOADING AND BE INSTALLED ACCORDINGLY.
- IF ANY EXISTING STRUCTURES TO REMAIN ARE DAMAGED DURING CONSTRUCTION IT SHA THE CONTRACTORS RESPONSIBILITY TO REPAIR AND/OR REPLACE THE EXISTING STRUCT AS NECESSARY TO RETURN IT TO EXISTING CONDITIONS OR BETTER.
- 8. ALL STORM SEWER MANHOLES IN PAVED AREAS SHALL BE FLUSH WITH PAVEMENT, AND S HAVE TRAFFIC BEARING RING & COVERS. MANHOLES IN UNPAVED AREAS SHALL BE 6" ABC FINISH GRADE. LIDS SHALL BE LABELED "STORM SEWER".
- 9. ALL STORM PIPE ENTERING STRUCTURES SHALL BE GROUTED TO ASSURE CONNECTION STRUCTURE IS WATERTIGHT.
- 10. ALL STORM STRUCTURES SHALL HAVE A SMOOTH UNIFORM POURED MORTAR INVERT FRO INVERT IN TO INVERT OUT.
- 11. ALL ROOF LEADERS FROM THE PROPOSED BUILDING SHALL CONNECT TO STORMWATER SYSTEM. SEE PLUMBING AND ARCHITECTURAL PLANS FOR DETAILS.
- 12. ALL PIPE LENGTHS SPECIFIED IN THESE PLANS ARE THE HORIZONTAL DISTANCE AND ARE SHOWN FOR REFERENCE ONLY. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO DETERMINE ACTUAL LENGTHS BASED ON PROPOSED PIPE SLOPE
- 13. ALL STORMWATER INFRASTRUCTURE ON THIS SITE IS PRIVATELY OWNED AND ANY MAINTENANCE OR REPLACEMENT IS THE OWNER'S RESPONSIBILITY.
- 14. SEE SHEETS C-07A THROUGH C-07C FOR DESCRIPTION OF DRAINAGE STRUCTURES.

TRAFFIC CONTROL NOTES

- 1. WHENEVER CONSTRUCTION OPERATIONS ENCROACH ON THE RIGHT-OF WAY OF ADJAC ROADWAYS, TRAFFIC CONTROL SHALL BE PROVIDED IN ACCORDANCE WITH LOCAL AND STANDARDS.
- 2. NO MATERIALS OR EQUIPMENT SHALL BE STORED OR STOCKPILED WITHIN THE RIGHT-O OF ADJACENT ROADWAYS.
- THE CONTRACTOR WILL BE SOLELY RESPONSIBLE FOR COMPLETING AND IMPLEMENTING TRAFFIC CONTROL PLAN.


GENERAL NOTES


1. THE AREA BETWEEN THE EXISTING RIGHT-OF-WAY LINE AND THE ULTIMATE RIGHT-OF-W/ LINE MUST BE DEDICATED TO THE AUTHORITY HAVING JURISDICTION OVER ANY PUBLIC STREETS FOR FUTURE TAKING, WHEN OR AS NECESSARY, AS REQUIRED BY SECTION 123 OF THE SUBDIVISION AND LAND DEVELOPMENT ORDINANCE


	UTIL	ITY NOTES			
	1.	EXISTING UNDERGROUND UTILITY INFORMATION PER SURVEY AND PLANS FROM CONTROL POINT ASSOCIATES, INC. CONTRACTOR SHALL NOTIFY ENGINEER IMMEDIATELY OF ANY DISCREPANCIES AND/OR CONFLICTS WITH EXISTING OR PROPOSED UTILITIES.			
ATUM NT HOWN FOR AND	2.	THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES, AND WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR MUST CALL THE APPROPRIATE UTILITY COMPANIES AT LEAST 72 HOURS BEFORE ANY EXCAVATION TO REQUEST EXACT FIELD LOCATION OF UTILITIES. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO RELOCATE ALL EXISTING UTILITIES WHICH CONFLICT WITH THE PROPOSED IMPROVEMENTS SHOWN ON THE PLANS.			sham nith
VITY	3.	THE CONTRACTOR SHALL FAMILIARIZE THEMSELVES WITH THE APPLICABLE UTILITY SERVICE PROVIDER REQUIREMENTS AND IS RESPONSIBLE FOR ALL COORDINATION REGARDING UTILITY DEMOLITION AS IDENTIFIED OR REQUIRED FOR PROJECT. THE CONTRACTOR SHALL PROVIDE THE OWNER WRITTEN NOTIFICATION THAT THE EXISTING UTILITIES AND SERVICES			Smith.com
	4.	HAVE BEEN TERMINATED AND ABANDONED IN ACCORDANCE WITH JURISDICTION AND UTILITY COMPANY REQUIREMENTS.	22	Suit	n Avenue South e 202 n, AL 35205
OR HALL S ARE RE A		ARCHITECTURAL DESIGN FOR EXACT BUILDING UTILITY CONNECTION LOCATIONS, DOOR ACCESS, AND EXTERIOR GRADING. THE UTILITY SERVICE SIZES ARE TO BE DETERMINED BY THE ARCHITECT. THE CONTRACTOR SHALL COORDINATE INSTALLATION OF UTILITIES/SERVICES WITH THE INDIVIDUAL SERVICE PROVIDERS, TO AVOID CONFLICTS AND ENSURE PROPER DEPTHS ARE ACHIEVED. THE JURISDICTION UTILITY REQUIREMENTS SHALL ALSO BE MET, AS WELL AS COORDINATING THE UTILITY TIE-INS/CONNECTIONS PRIOR TO CONNECTING TO THE EXISTING UTILITY/SERVICE. WHERE CONFLICTS EXIST WITH THESE SITE PLANS, ENGINEER IS TO BE NOTIFIED PRIOR TO CONSTRUCTION TO RESOLVE.		,	Horn Engineers, inc.
	5.	THE CONTRACTOR SHALL PERFORM WHATEVER TEST EXCAVATION OR OTHER INVESTIGATION IS NECESSARY TO VERIFY TIE-IN INVERTS, LOCATIONS AND CLEARANCES, AND SHALL REPORT IMMEDIATELY ANY DISCREPANCIES TO KIMLEY- HORN AND ASSOCIATES, INC.			
.8% IN	6.	THE CONTRACTOR IS RESPONSIBLE FOR THE PROTECTION OF ALL UTILITIES TO REMAIN IN PLACE.	ŏč	5:	
DF 1.8% DICAP ESIGN	7.	CROSS CONNECTION CONTROL AND BACK FLOW PREVENTION SHALL BE IN ACCORDANCE WITH THE UNIFORM STATEWIDE BUILDING CODE.	q	🔫 End	compass
RLF	8.	ALL CLEANOUTS WITHIN VEHICULAR AREAS SHALL BE TRAFFIC BEARING.	q	5 He	alth
	9.	CONTRACTOR SHALL SAW CUT, REMOVE, AND REPLACE ASPHALT PAVEMENT AS NECESSARY TO INSTALL UNDERGROUND ELECTRIC, TELEPHONE, SANITARY SEWER, WATER, AND COMMUNICATION CONDUITS.			
L BE JRES.	10.	UNDERGROUND UTILITIES INSTALLED ON PRIVATE PROPERTY OR IN PRIVATE UTILITY EASEMENTS AND BUILDING RELATED STORM DRAINS SHALL BE DESIGNED AND INSTALLED PER THE CURRENT EDITION OF THE PENNSYLVANIA BUILDING CODE.		ITAI	OPMENT 19403
IATION	11.	PROPOSED CROSSINGS WITH EXISTING UNDERGROUND UTILITIES SHALL BE FIELD VERIFIED BY TEST PIT PRIOR TO COMMENCEMENT OF CONSTRUCTION.	Ţ	SPI	
NTACT	12.	THE RIM ELEVATIONS OF EXISTING MANHOLES AND SANITARY CLEANOUT TOPS SHALL BE ADJUSTED, IF REQUIRED, TO MATCH PROPOSED GRADES IN ACCORDANCE WITH ALL APPLICABLE STANDARDS.			DEV own,
	13.	ALL UTILITY CONNECTIONS END AT 5' OUTSIDE THE BUILDING FOOTPRINT. REFER TO ARCHITECTURAL, MECHANICAL, ELECTRICAL, AND PLUMBING PLANS FOR BUILDING LAYOUT AND INTERNAL UTILITY SERVICE.	E H	$\square \bigcirc$	L LAND, Norristo
IC ALL BE	14.	ALL PIPE LENGTHS SPECIFIED IN THESE PLANS ARE THE HORIZONTAL DISTANCE AND ARE SHOWN FOR REFERENE ONLY. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO DETERMINE ACTUAL LENGTHS BASED ON PROPOSED PIPE SLOPE. PIPE LENGTHS IN PLANS ARE MEASURED FROM CENTER OF STRUCTURE TO CENTER OF STRUCTURE UNLESS OTHERWISE NOTED.	NPAS		PRELIMINARY/FINAL 2660 Audubon Road, I
TURE	15.	ALL FILL MATERIAL IS TO BE IN PLACE, AND COMPACTED BEFORE INSTALLATION OF PROPOSED UTILITIES.		NO	-IMIN/ Audu
SHALL OVE	16.	ALL UTILITIES SHOULD BE KEPT TEN (10) FEET APART (PARALLEL) OR WHEN CROSSING 18" VERTICAL CLEARANCE (OUTSIDE EDGE OF PIPE TO OUTSIDE EDGE OF PIPE) UNLESS OTHERWISE NOTED ON PLANS.	Р И Ц	Ш П П П С	PREL 2660
AT OM	17.	CONTRACTOR SHALL MAINTAIN A MINIMUM OF FOURTY-EIGHT (48) INCH COVER ON ALL WATERLINES.			
	18.	IN THE EVENT OF A VERTICAL CONFLICT BETWEEN WATERLINES, SANITARY LINES, STORM LINES AND GAS LINES, (EXISTING AND PROPOSED), THE SANITARY LINE SHALL BE DUCTILE IRON PIPE WITH MECHANICAL JOINTS AT LEAST TEN (10) FEET ON BOTH SIDES OF CROSSING, THE WATERLINE SHALL HAVE MECHANICAL JOINTS WITH APPROPRIATE THRUST BLOCKING AS REQUIRED TO PROVIDE A MINIMUM OF EIGHTEEN (18) INCH CLEARANCE. MEETING REQUIREMENTS OF ANSI A21.10 OR ANSI 21.11 (AWWA C-151) (CLASS 50).			
	19.	LINES UNDERGROUND SHALL BE INSTALLED, INSPECTED, AND APPROVED BEFORE BACKFILLING.			
	20.	ALL CONCRETE FOR ENCASEMENTS SHALL HAVE A MINIMUM 28 DAY COMPRESSION STRENGTH AT 3000 P.S.I.			
	21.	EXISTING UTILITIES SHALL BE VERIFIED IN FIELD PRIOR TO INSTALLATION OF ANY NEW LINES.		Rev	vision
ENT STATE	22. 23.	REFER TO INTERIOR PLUMBING DRAWINGS FOR TIE-IN OF ALL UTILITIES. CONTRACTOR IS RESPONSIBLE FOR COMPLYING WITH AUDUBON WATER COMPANY AND LOWER PROVIDENCE TOWNSHIP SEWER AUTHORITY SPECIFICATIONS WITH REGARDS TO	No.	Date	Description
F-WAY	24.	MATERIALS AND INSTALLATION OF THE WATER AND SEWER LINES. ALL WATER LINE CONSTRUCTION TO CONFORM TO APPLICABLE AUDUBON WATER COMPANY SPECIFICATIONS.			
G	25.	THE CONTRACTOR SHALL VERIFY ALL WATERLINE SIZES PRIOR TO PURCHASE AND INSTALLATION.			
	26.	COORDINATE WITH LOCAL ELECTRIC SERVICE PROVIDER FOR PROPOSED ELECTRIC CONNECTION.			
/AY 23-31.K	27.	COORDINATE WITH LOCAL GAS SERVICE PROVIDER FOR TYING PROPOSED GAS LINE INTO EXISTING GAS LINE.			
	28.	THE SITE CONTRACTOR SHALL COORDINATE SERVICE ROUTING OF ALL GAS, TELEPHONE, AND ELECTRICAL LINES WITH THE APPROPRIATE UTILITY COMPANY. ALL CONSTRUCTION MUST COMPLY WITH EACH UTILITY'S STANDARDS AND SPECIFICATIONS AND NOT INTERFERE WITH TREE PLANTING SITES OR EXISTING TREES TO BE PRESERVED.			
	29.	CONTRACTOR TO CALL FOR INSPECTION WHEN EXISTING SEWER IS BEING TAPPED INTO PROPOSED LINE.			
		CALL BEFORE YOU DIG! PENNSYLVANA LAW REQUIRES 3 WORKING DAYS NOTCE FOR CONSTRUCTION PHASE AND 10 WORKING DAYS IN DESIGN STAGE – STOP CALL	C		AL NOTES
		PRELIMINARY NOT FOR CONSTRUCTION		1126	- 01


This Line is 3 Inches When Printed Full Size


08/30/2023












Jrawn By: J



DETECTABLE WARNING SURFACE (TYP)		GreshamS	mith.com
TURNING SPACE WIDTH 5'-0" MIN <u>TYPE 2</u> PLAIN CEMENT CONCRETE		Suite	Avenue South 202 , AL 35205
CURB_RAMP DEPRESSED CORB	Ki	mley	»Horn
R S OF JLK. PLAIN CEMENT CONCRETE JLK. PLAIN CEMENT CONCRETE DEPRESSED CURB UNT DEWALK ECTION DEVALK			ENGINEERS, INC. CIVIL GEOTECHNICAL
WIDTH OF TURNING SPACE AT DEPRESSED CURB TO MATCH WIDTH OF DETECTABLE WARNING SURFACE	ŧ	Enc Hec	ompass 11th
I THE 2 URB RAME ASSISTANT DISTRICT EXECUTIVE APPROVAL RECURRED LF TURING SPACE IS NOT ENTIRELY ON SIDEWALK	ENCOMPASS HEALTH	OF NORRISTOWN	PRELIMINARY/FINAL LAND DEVELOPMENT 2660 Audubon Road, Norristown, PA 19403
JSHBUTTON DETAILS NOT SHOWN. ITED DOMES ON A SQUARE GRID IN THE PREDOMINANT DIRECTION OF THE RAMP AND INSTALLATIONS ALONG CURVED SURFACES. S) 24" MINIMUM (IN THE DIRECTION OF PEDESTRIAN TRAVEL) ACROSS FULL WIDTH OF GE. PROVIDE DWS THAT CONTRAST VISUALLY WITH ADJACENT WALKWAY SURFACES, FOR THE FULL WIDTH OF RAMP. 0% CROSS SLOPE ON THE CURB RAMP OR PEDESTRIAN ACCESS ROUTE. ONSTRUCT CURB RAMP FAND FLARE SLOPES WITH THE FLATTEST SLOPE POSSIBLE. THE			
MAX SLOPE ALLOWABLE. SLOPES THAT EXCEED THOSE INDICATED IN THE DETAILS, OR NOT BE ACCEPTED AND WILL BE RECONSTRUCTED. OPE NOT TO EXCEED 5.00%, FOR ROADWAY PROFILE SLOPES THAT EXCEED 5.00%, O ROADWAY AT A LONGITUDINAL SLOPE NOT TO EXCEED ROADWAY PROFILE SLOPE. HE CURB RAMP AND ADJOINING ROAD SURFACE IS NOT TO EXCEED AN ALGEBRAIC OF THE GUTTER OR ROAD AT THE FOOT OF A CURB RAMP, TURNING SPACE OR %. SEE SHEET 8 FOR DETAILS.			
MOST APPROPRIATE FOR NEW CONSTRUCTION. ALL CONSTRUCTION MUST MEET THE WISE NOTED OR DIRECTED.	No.	Revi Date	sion Description
 a Level plane. Therefore, the length of RAMP is Not Solely Dependant on URB DOES NOT NECESSARILY MEAN A RAMP LENgth of 6'-0" FOR A 12:1 SLOPE.) when passing areas 5'-0" x 5'-0" are provided every 200'. E EDGE OF THE WHITE PAVEMENT MARKING LINE. IF A WHITE PAVEMENT MARKING LINE DOES THE CONTRACT DOCUMENTS. PS FLUSH TO ADJACENT ROADWAY. GRADE EDGE OF ROAD ELEVATIONS AT THE FLOW LINE PONDING. FOR LEVEL TURNING SPACES BEHIND DEPRESSED CURB, ADJUST SLOPES TO THE CONTRACT DOCUMENTS. T TO NON-WALK AREAS OF ELEVATION DIFFERENCES CANNOT BE ACCOMMODATED BY ROTHER NON-WALK AREAS AT 3:1 OR FLATTER. DO NOT INSTALL CHEEK WALLS THAT DEPRESSED CURB TO BE FLUSH WITH ADJACENT SURFACES (RAMPS, SIDEWALKS, FLARES). ROSSWALK, THE RAMP (EXCLUDING FLARES) TO BE FULLY INSIDE OF MARKED CROSSWALK BE USED TO VERIFY THE SLOPES OF CURB RAMPS AND SIDEWALKS. IG SPACES, FLARES, AND SIDEWALKS ABUT. H ROADWAY PROFILE AND HAVE A FLUSH CONNECTION, TRANSITION CURB RAMP CROSS LUALLY AS POSSIBLE. DO NOT EXCEED JOINT SET OF COSS SLOPE RATE OF CHANGE DO SUFFACES. LINES SHOWN ON DETAILS ARE FOR ILLUSTRATION ONLY. SEE NOTE 5. JTHCALLY WITH CURB RAMP, SIDE FLARES, OR BOTH. DO NOT PLACE DEPRESSED CURB 			
WEALTH OF PENNSYLVANIA of transportation of project delivery MPS and sidewalks			
CONSTRUCTION OR ERATION DETAILS CURB RAMPS AND PICAL SECTIONS - RECOMMENDED DEC. 17, 2019 SHT 1 OF 14 DIRECTOR, BUREAU OF PROJECT DELIVERY RC-67M		SITE DET	AILS
PRELIMINARY NOT FOR CONSTRUCTION	C	11264 08/30/	
	This Li	ine is 3 Inches V	Vhen Printed Full Size


, , , , , , , , , , , , , , , NON-WALK SURFACE

-PEDESTRIAN PUSHBUTTON (WHERE APPLICABLE SEE SHEET 8 FOR DETAILS)


PLAIN CEMENT CONCRETE CURB CHEEK WALL (SEE NOTE 23, SHEET 1)

Gresham


Smith





Ę





		Gres	ham hith
	22	Suite	Smith.com Avenue South 202 n, AL 35205
		Kimley	»Horn
	啼		ENGINEERS, INC.
		65	joe ®
	đ	Find Hea	ompass alth
	MPASS HEALTH	REHABILITATION HOSPITAL OF NORRISTOWN	PRELIMINARY/FINAL LAND DEVELOPMENT 2660 Audubon Road, Norristown, PA 19403
	ENCO	REH	PRELIM 2660 Au
		Rev	ision
	No.	Date	Description
CALL BEFORE YOU DIG! PENNSYLVANIA LAW REQUIRES 3 WORKING DAYS NOTICE FOR CONSTRUCTION PHASE AND 10 WORKING DAYS IN DESIGN STAGE – STOP CALL WWENTER. DAYS IN DESIGN STAGE – STOP CALL WWENTER. PARA 1 1-800-242-1776 SERIAL NUMBER: 20221403029 DATE REQUESTED: 05/20/2022	(CONSTF	GAS RUCTION AILS
PRELIMINARY NOT FOR CONSTRUCTION		1126/ 08/30)4E 42001 1/2023
































EROSION CONTROL NOTES

- ALL EARTH DISTURBANCES, INCLUDING CLEARING AND GRUBBING AS WELL AS CUTS AND FILLS SHALL BE DONE IN ACCORDANCE WITH THE APPROVED E&S PLAN. A COPY OF THE APPROVED DRAWINGS (STAMPED, SIGNED AND DATED BY THE REVIEWING AGENCY) MUST BE AVAILABLE AT THE PROJECT SITE AT ALL TIMES. THE REVIEWING AGENCY SHALL BE NOTIFIED OF ANY CHANGES TO THE APPROVED PLAN PRIOR TO IMPLEMENTATION OF THOSE CHANGES. THE REVIEWING AGENCY MAY REQUIRE A WRITTEN SUBMITTAL OF THOSE CHANGES FOR REVIEW AND APPROVAL AT ITS DISCRETION.
- AT LEAST 7 DAYS PRIOR TO STARTING ANY EARTH DISTURBANCE ACTIVITIES, INCLUDING CLEARING AND GRUBBING, THE OWNER AND/OR OPERATOR SHALL INVITE ALL CONTRACTORS, THE LANDOWNER, APPROPRIATE MUNICIPAL OFFICIALS, THE E&S PLAN PREPARER, THE PCSM PLAN PREPARER. THE LICENSED PROFESSIONAL RESPONSIBLE FOR OVERSIGHT OF CRITICAL STAGES OF IMPLEMENTATION OF THE PCSM PLAN, AND A REPRESENTATIVE FROM THE LOCAL CONSERVATION DISTRICT TO AN ON-SITE PRE-CONSTRUCTION MEETING
- AT LEAST 3 DAYS PRIOR TO STARTING ANY EARTH DISTURBANCE ACTIVITIES, OR EXPANDING INTO AN AREA PREVIOUSLY UNMARKED, THE PENNSYLVANIA ONE CALL SYSTEM INC. SHALL BE NOTIFIED AT 1-800-242-1776 FOR THE LOCATION OF EXISTING UNDERGROUND UTILITIES.
- ALL EARTH DISTURBANCE ACTIVITIES SHALL PROCEED IN ACCORDANCE WITH THE SEQUENCE PROVIDED ON THE PLAN DRAWINGS. DEVIATION FROM THAT SEQUENCE MUST BE APPROVED IN WRITING FROM THE LOCAL CONSERVATION DISTRICT OR BY THE DEPARTMENT PRIOR TO IMPI EMENTATION
- AREAS TO BE FILLED ARE TO BE CLEARED, GRUBBED, AND STRIPPED OF TOPSOIL TO REMOVE TREES VEGETATION ROOTS AND OTHER OBJECTIONABLE MATERIAL
- CLEARING, GRUBBING, AND TOPSOIL STRIPPING SHALL BE LIMITED TO THOSE AREAS DESCRIBED IN EACH STAGE OF THE CONSTRUCTION SEQUENCE. GENERAL SITE CLEARING, GRUBBING AND TOPSOIL STRIPPING MAY NOT COMMENCE IN ANY STAGE OR PHASE OF THE PROJECT UNTIL THE E&S BMPS SPECIFIED BY THE BMP SEQUENCE FOR THAT STAGE OR PHASE HAVE BEEN INSTALLED AND ARE FUNCTIONING AS DESCRIBED IN THIS E&S PLAN.
- AT NO TIME SHALL CONSTRUCTION VEHICLES BE ALLOWED TO ENTER AREAS OUTSIDE THE LIMIT OF DISTURBANCE BOUNDARIES SHOWN ON THE PLAN MAPS. THESE AREAS MUST BE CLEARLY MARKED AND FENCED OFF BEFORE CLEARING AND GRUBBING OPERATIONS BEGIN.
- TOPSOIL REQUIRED FOR THE ESTABLISHMENT OF VEGETATION SHALL BE STOCKPILED AT THE LOCATION(S) SHOWN ON THE PLAN MAPS(S) IN THE AMOUNT NECESSARY TO COMPLETE THE FINISH GRADING OF ALL EXPOSED AREAS THAT ARE TO BE STABILIZED BY VEGETATION FACH STOCKPILE SHALL BE PROTECTED IN THE MANNER SHOWN ON THE PLAN DRAWINGS. STOCKPILE HEIGHTS SHALL NOT EXCEED 35 FEET. STOCKPILE SLOPES SHALL BE 2H:1V OR FLATTER. IMMEDIATELY UPON DISCOVERING UNFORESEEN CIRCUMSTANCES POSING THE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT POLLUTION, THE OPERATOR SHALL IMPLEMENT APPROPRIATE BEST MANAGEMENT PRACTICES TO MINIMIZE THE POTENTIAL FOR EROSION AND
- SEDIMENT POLLUTION AND NOTIFY THE LOCAL CONSERVATION DISTRICT AND/OR THE REGIONAL OFFICE OF THE DEPARTMENT. ALL BUILDING MATERIALS AND WASTES SHALL BE REMOVED FROM THE SITE AND RECYCLED OR DISPOSED OF IN ACCORDANCE WITH THE DEPARTMENT'S SOLID WASTE MANAGEMENT
- REGULATIONS AT 25 PA. CODE 260.1 ET SEQ., 271.1, AND 287.1 ET. SEQ. NO BUILDING MATERIALS OR WASTES OR UNUSED BUILDING MATERIALS SHALL BE BURNED, BURIED, DUMPED, OR DISCHARGED AT THE SITE.
- ALL OFF-SITE WASTE AND BORROW AREAS MUST HAVE AN E&S PLAN APPROVED BY THE LOCAL CONSERVATION DISTRICT OR THE DEPARTMENT FULLY IMPLEMENTED PRIOR TO BEING ACTIVATED
- THE CONTRACTOR IS RESPONSIBLE FOR ENSURING THAT ANY MATERIAL BROUGHT ON SITE IS CLEAN FILL. FORM FP-001 MUST BE RETAINED BY THE PROPERTY OWNER FOR ANY FILL MATERIAL AFFECTED BY A SPILL OR RELEASE OF A REGULATED SUBSTANCE BUT QUALIFYING AS CLEAN FILL DUE TO ANALYTICAL TESTING.
- 13. ALL PUMPING OF WATER FROM ANY WORK AREA SHALL BE DONE ACCORDING TO THE PROCEDURE DESCRIBED IN THIS PLAN, OVER UNDISTURBED VEGETATED AREAS.
- 14. VEHICLES AND EQUIPMENT MAY ENTER FROM AUDUBON ROAD. 15. UNTIL THE SITE IS STABILIZED, ALL EROSION AND SEDIMENT BMPS SHALL BE MAINTAINED PROPERLY. MAINTENANCE SHALL INCLUDE INSPECTIONS OF ALL EROSION AND SEDIMENT BMPS AFTER EACH RUNOFF EVENT AND ON A WEEKLY BASIS. ALL PREVENTATIVE AND REMEDIAL MAINTENANCE WORK, INCLUDING CLEAN OUT, REPAIR, REPLACEMENT, REGRADING, RESEEDING, REMULCHING AND RENETTING MUST BE PERFORMED IMMEDIATELY. IF THE E&S BMPS FAIL TO PERFORM AS EXPECTED, REPLACEMENT BMPS, OR MODIFICATIONS OF THOSE INSTALLED WILL BE REQUIRED.
- 16. A LOG SHOWING DATES THAT E&S BMPS WERE INSPECTED AS WELL AS ANY DEFICIENCIES FOUND AND THE DATE THEY WERE CORRECTED SHALL BE MAINTAINED ON THE SITE AND BE MADE AVAILABLE TO REGULATORY AGENCY OFFICIALS AT THE TIME OF INSPECTION.
- SEDIMENT TRACKED ONTO ANY PUBLIC ROADWAY OR SIDEWALK SHALL BE RETURNED TO THE CONSTRUCTION SITE BY THE END OF EACH WORK DAY AND DISPOSED IN THE MANNER DESCRIBED IN THIS PLAN. IN NO CASE SHALL THE SEDIMENT BE WASHED, SHOVELED, OR SWEPT INTO ANY ROADSIDE DITCH, STORM SEWER, OR SURFACE WATER.
- 18. ALL SEDIMENT REMOVED FROM BMPS SHALL BE DISPOSED OF IN THE MANNER DESCRIBED ON THE PLAN DRAWINGS AREAS WHICH ARE TO BE TOPSOILED SHALL BE SCARIFIED TO A MINIMUM DEPTH OF 3 TO 5 INCHES
- -- 6 TO 12 INCHES ON COMPACTED SOILS PRIOR TO PLACEMENT OF TOPSOIL. AREAS TO BE VEGETATED SHALL HAVE A MINIMUM 4 INCHES OF TOPSOIL IN PLACE PRIOR TO SEEDING AND MULCHING. FILL OUTSLOPES SHALL HAVE A MINIMUM OF 2 INCHES OF TOPSOIL. ALL FILLS SHALL BE COMPACTED AS REQUIRED TO REDUCE EROSION, SLIPPAGE, SETTLEMENT,
- SUBSIDENCE OR OTHER RELATED PROBLEMS FILL INTENDED TO SUPPORT BUILDINGS STRUCTURES AND CONDUITS, ETC. SHALL BE COMPACTED IN ACCORDANCE WITH LOCAL REQUIREMENTS OR CODES.
- 21. ALL EARTHEN FILLS SHALL BE PLACED IN COMPACTED LAYERS NOT TO EXCEED 8 INCHES IN THICKNESS. 22. FILL MATERIALS SHALL BE FREE OF FROZEN PARTICLES, BRUSH, ROOTS, SOD, OR OTHER FOREIGN
- OR OBJECTIONABLE MATERIALS THAT WOULD INTERFERE WITH OR PREVENT CONSTRUCTION OF SATISFACTORY FILLS. 23. FROZEN MATERIALS OR SOFT, MUCKY, OR HIGHLY COMPRESSIBLE MATERIALS SHALL NOT BE
- INCORPORATED INTO FILLS. 24. FILL SHALL NOT BE PLACED ON SATURATED OR FROZEN SURFACES.
- 25. SEEPS OR SPRINGS ENCOUNTERED DURING CONSTRUCTION SHALL BE HANDLED IN ACCORDANCE WITH THE STANDARD AND SPECIFICATION FOR SUBSURFACE DRAIN OR OTHER APPROVED METHOD.
- 26. ALL GRADED AREAS SHALL BE PERMANENTLY STABILIZED IMMEDIATELY UPON REACHING FINISHED GRADE. CUT SLOPES IN COMPETENT BEDROCK AND ROCK FILLS NEED NOT BE VEGETATED. SEEDED AREAS WITHIN 50 FEET OF A SURFACE WATER, OR AS OTHERWISE SHOWN
- ON THE PLAN DRAWINGS. SHALL BE BLANKETED ACCORDING TO THE STANDARDS OF THIS PLAN IMMEDIATELY AFTER EARTH DISTURBANCE ACTIVITIES CEASE IN ANY AREA OR SUBAREA OF THE PROJECT, THE OPERATOR SHALL STABILIZE ALL DISTURBED AREAS. DURING NON-GERMINATING MONTHS, MULCH OR PROTECTIVE BLANKETING SHALL BE APPLIED AS DESCRIBED IN THE PLAN. AREAS NOT AT FINISHED GRADE, WHICH WILL BE REACTIVATED WITHIN 1 YEAR, MAY BE STABILIZED IN ACCORDANCE WITH THE TEMPORARY STABILIZATION SPECIFICATIONS. THOSE AREAS WHICH WILL NOT BE REACTIVATED WITHIN 1 YEAR SHALL BE STABILIZED IN ACCORDANCE WITH THE PERMANENT STABILIZATION SPECIFICATIONS.
- . PERMANENT STABILIZATION IS DEFINED AS A MINIMUM UNIFORM, PERENNIAL 70% VEGETATIVE COVER OR OTHER PERMANENT NON-VEGETATIVE COVER WITH A DENSITY SUFFICIENT TO RESIST ACCELERATED EROSION. CUT AND FILL SLOPES SHALL BE CAPABLE OF RESISTING FAILURE DUE TO SLUMPING, SLIDING, OR OTHER MOVEMENTS.
- 29. E&S BMPS SHALL REMAIN FUNCTIONAL AS SUCH UNTIL ALL AREAS TRIBUTARY TO THEM ARE PERMANENTLY STABILIZED OR UNTIL THEY ARE REPLACED BY ANOTHER BMP APPROVED BY THE LOCAL CONSERVATION DISTRICT OR THE DEPARTMENT.
- 0. UPON COMPLETION OF ALL EARTH DISTURBANCE ACTIVITIES AND PERMANENT STABILIZATION OF ALL DISTURBED AREAS, THE OWNER AND/OR OPERATOR SHALL CONTACT THE LOCAL CONSERVATION DISTRICT FOR AN INSPECTION PRIOR TO REMOVAL/CONVERSION OF THE E&S BMPS
- AFTER FINAL SITE STABILIZATION HAS BEEN ACHIEVED, TEMPORARY EROSION AND SEDIMENT BMPS MUST BE REMOVED OR CONVERTED TO PERMANENT POST CONSTRUCTION STORMWATER MANAGEMENT BMPS. AREAS DISTURBED DURING REMOVAL OR CONVERSION OF THE BMPS SHALL BE STABILIZED IMMEDIATELY. IN ORDER TO ENSURE RAPID REVEGETATION OF DISTURBED AREAS, SUCH REMOVAL/CONVERSIONS ARE TO BE DONE ONLY DURING THE GERMINATING SEASON.
- 32. UPON COMPLETION OF ALL EARTH DISTURBANCE ACTIVITIES AND PERMANENT STABILIZATION OF ALL DISTURBED AREAS, THE OWNER AND/OR OPERATOR SHALL CONTACT THE LOCAL CONSERVATION DISTRICT TO SCHEDULE A FINAL INSPECTION
- . FAILURE TO CORRECTLY INSTALL E&S BMPS, FAILURE TO PREVENT SEDIMENT-LADEN RUNOFF FROM LEAVING THE CONSTRUCTION SITE, OR FAILURE TO TAKE IMMEDIATE CORRECTIVE ACTION TO RESOLVE FAILURE OF F&S BMPS MAY RESULT IN ADMINISTRATIVE CIVIL AND/OR CRIMINAL PENALTIES BEING INSTITUTED BY THE DEPARTMENT AS DEFINED IN SECTION 602 OF THE PENNSYLVANIA CLEAN STREAMS LAW. THE CLEAN STREAMS LAW PROVIDES FOR UP TO \$10,000 PER DAY IN CIVIL PENALTIES, UP TO \$10,000 IN SUMMARY CRIMINAL PENALTIES, AND UP TO \$25,000 IN MISDEMEANOR CRIMINAL PENALTIES FOR EACH VIOLATION
- CONCRETE WASH WATER SHALL BE HANDLED IN THE MANNER DESCRIBED ON THE PLAN DRAWINGS. IN NO CASE SHALL IT BE ALLOWED TO ENTER ANY SURFACE WATERS OR GROUNDWATER SYSTEMS
- 35. EROSION CONTROL BLANKETING SHALL BE INSTALLED ON ALL SLOPES 3H:1V OR STEEPER WITHIN 50 FEET OF A SURFACE WATER AND ON ALL OTHER DISTURBED AREAS SPECIFIED ON THE PLAN MAPS AND/OR DETAIL SHEETS.
- 36. FILL MATERIAL FOR EMBANKMENTS SHALL BE FREE OF ROOTS, OR OTHER WOODY VEGETATION, ORGANIC MATERIAL, LARGE STONES, AND OTHER OBJECTIONABLE MATERIALS.

CONSTRUCTION INSPECTION & MAINTENANCE PROGRAM THE FOLLOWING MAINTENANCE PROGRAM HAS BEEN DEVELOPED TO PROVIDE FOR THE INSPECTION OF BMPS ON A WEEKLY BASIS AND AFTER EACH MEASURABLE RUNOFF EVENT, AND TO INCLUDE THE REPAIR OF THE BMPS TO ENSURE THEIR EFFECTIVE AND EFFICIENT OPERATION:

CONTRACTOR SHALL MAINTAIN AND MAKE AVAILABLE TO THE MUNICIPALITY COMPLETE, WRITTEN INSPECTION LOGS OF THE ABOVE NOTED INSPECTION AND MAINTENANCE

UNTIL THE SITE IS STABILIZED AND DURING CONSTRUCTION ACTIVITIES, ALL BMPS MUST BE MAINTAINED PROPERLY BY THE CONTRACTOR. MAINTENANCE MUST INCLUDE INSPECTIONS OF ALL BMPS AFTER EACH RUNOFF EVENT AND ON A WEEKLY BASIS. ALL PREVENTATIVE AND REMEDIAL MAINTENANCE WORK, INCLUDING CLEAN-OUT, REPAIR, REPLACEMENT, REGRADING, RESEEDING, REMULCHING, AND RENETTING MUST BE PERFORMED IMMEDIATELY AND IN ACCORDANCE WITH THESE PROCEDURES, PLANS AND DETAILS. ANY AREAS DISTURBED DURING MAINTENANCE MUST BE STABILIZED IMMEDIATELY IN ACCORDANCE WITH THE GENERAL CONSERVATION NOTES AND SPECIFICATIONS. ALL SITE INSPECTIONS MUST BE DOCUMENTED IN AN INSPECTION LOG KEPT FOR THIS PURPOSE INDICATING THE COMPLIANCE ACTIONS AND THE DATE, TIME AND NAME OF THE PERSON CONDUCTING THE INSPECTION. THE INSPECTION LOG MUST BE KEPT ON SITE AT ALL TIMES AND MADE AVAILABLE TO THE DISTRICT UPON REQUEST.

- **1. ROCK CONSTRUCTION ENTRANCE** ROCK CONSTRUCTION ENTRANCE THICKNESS SHALL BE CONSTANTLY MAINTAINED TO THE SPECIFIED DIMENSIONS BY ADDING ROCK. A STOCKPILE OF ROCK MATERIAL SHALL BE MAINTAINED ON SITE FOR THIS PURPOSE. DRAIN SPACE UNDER WASH RACK SHALL BE KEPT OPEN AT ALL TIMES. DAMAGE TO THE WASH RACK SHALL BE REPAIRED PRIOR TO FURTHER USE OF THE RACK. ALL SEDIMENT DEPOSITED ON ROADWAYS SHALL BE REMOVED AND RETURNED TO THE CONSTRUCTION SITE IMMEDIATELY. WASHING THE ROADWAY OR SWEEPING THE DEPOSITS INTO ROADWAY DITCHES, SEWERS, CULVERTS, OR OTHER DRAINAGE COURSES IS NOT ACCEPTABLE
- 2. COMPOST FILTER SOCKS INSPECTIONS SHALL BE CONDUCTED ON A WEEKLY BASIS AND/OR AFTER EACH RUNOFF EVENT. NEEDED REPAIRS SHOULD BE INITIATED IMMEDIATELY AFTER THE INSPECTION. SEDIMENT MUST BE REMOVED WHEN ACCUMULATIONS REACH ½ THE ABOVE GROUND HEIGHT OF THE SOCK. THE SEDIMENT SHALL BE DISPOSED OF ON-SITE AND/OR IN ACCORDANCE WITH APPLICABLE LOCAL. STATE AND FEDERAL REGULATIONS.
- 3. INLET PROTECTION (FILTER BAG) SEDIMENT SHALL BE REMOVED WHEN IT REACHES HALF THE HEIGHT OF THE BAG. DAMAGED OR CLOGGED INSTALLATIONS SHALL BE REPAIRED OR REPLACED **IMMEDIATELY**
- 4. VEGETATIVE SURFACE STABILIZATION SEEDED AREAS THAT HAVE WASHED AWAY SHALL BE FILLED AND GRADED AS NECESSARY AND THEN RESEEDED. A BURLAP OR STRAW COVER WILL BE APPLIED TO RETAIN THE SEED UNTIL IT HAS A CHANCE TO ROOT PROPERLY
- 5. COMPOST SOCK CONCRETE WASHOUT FACILITY ALL FACILITIES SHALL BE INSPECTED DAILY. DAMAGED OR LEAKING WASHOUTS SHOULD BE DEACTIVATED AND REPAIRED OR REPLACED IMMEDIATELY. ACCUMULATED MATERIALS SHOULD BE REMOVED WHEN THEY REACH 75% CAPACITY. PLASTIC LINERS SHALL BE REPLACED WITH EACH CLEANING OF THE WASHOUT FACILITY.
- 6. TEMPORARY STOCKPILES NEEDED MAINTENANCE SHOULD BE INITIATED IMMEDIATELY AFTER THE INSPECTION. ANY AREAS DISTURBED DURING MAINTENANCE MUST BE STABILIZED IMMEDIATELY IN ACCORDANCE WITH THE GENERAL CONSERVATION NOTES AND SPECIFICATIONS.
- 7. RIPRAP APRON ALL APRONS SHALL BE INSPECTED AT LEAST WEEKLY AND AFTER EACH RUNOFF EVENT. DISPLACED RIPRAP WITHIN THE APRON SHALL BE REPLACED IMMEDIATELY.
- 8. PUMPED WATER FILTER BAG (IF WARRANTED) A SUITABLE MEANS OF ACCESSING THE BAG WITH MACHINERY REQUIRED FOR DISPOSAL PURPOSES SHALL BE PROVIDED. FILTER BAGS SHALL BE REPLACED WHEN THEY BECOME ½ FULL OF SEDIMENT. SPARE BAGS SHALL BE KEPT AVAILABLE FOR REPLACEMENT OF THOSE THAT HAVE FAILED OR ARE FILLED. BAGS SHALL BE PLACED ON STRAPS TO FACILITATE REMOVAL UNLESS BAGS COME WITH LIFTING STRAPS ALREADY ATTACHED.
- 9. SEEDING, MULCHING AND FERTILIZING SHALL BE IN ACCORDANCE WITH THE SEEDING AND MULCHING SCHEDULE.
- 10. SHOULD THE TREE PROTECTION FENCING BE DISTURBED AT ANY POINT, IT SHALL BE REPLACED IMMEDIATELY
- 11. THE CONTRACTOR SHALL HAVE AVAILABLE WATER TRUCKS OR OTHER MEANS OF CONTROLLING EXCESSIVE DUST AND AIRBORNE DEBRIS.
- 12. ALL DRAINAGE SWALES SHALL BE SEEDED AND MULCHED, AND PROTECTED WITH TURF REINFORCEMENT MAT: NORTH AMERICAN GREEN, AS INDICATED ON PLANS. IF SWALES ARE TO BE SODDED, TURF REINFORCEMENT IS NOT REQUIRED.
- 13. ALL AREAS OF CONCENTRATED SURFACE DRAINAGE SHALL BE SEEDED AND MULCHED, AND PROTECTED WITH TEMPORARY TURF REINFORCEMENT MAT: NORTH AMERICAN GREEN, AS INDICATED ON PLANS. IF AREAS ARE TO BE SODDED, TURF REINFORCEMENT IS NOT REQUIRED.
- 14. AFTER THE STORM CONVEYANCE SYSTEM IS CONSTRUCTED, MONTHLY INSPECTIONS FOR EACH DEVICE WILL BE MADE. AN INSPECTION OF ALL FACILITIES WILL BE MADE AFTER EVERY STORM TO DETERMINE THEIR RESISTANCE TO DRIVING RAINS AND ACCUMULATED RUNOFF
- 15. SEEDED AREAS THAT HAVE WASHED AWAY SHALL BE FILLED AND GRADED AS NECESSARY AND THEN RESEEDED. A BURLAP OR STRAW COVER WILL BE APPLIED TO RETAIN THE SEED UNTIL IT HAS A CHANCE TO ROOT PROPERLY.
- 16. THE ABOVE PROCEDURE SHALL BE REPEATED AFTER EACH SIZABLE STORM UNTIL NO MORE SIGNS OF EROSION ARE EVIDENT. AT MONTHLY INTERVALS THEREAFTER, INSPECTIONS AND NECESSARY CLEANING WILL BE DONE. TRASH THAT IS REMOVED FROM ANY OF THE CONTROL DEVICES SHALL BE DISPOSED OF AT AN APPROVED DISPOSAL AREA. SILT THAT HAS ACCUMULATED SHALL BE REMOVED AND ALLOWED TO DRY AND USED AS FILL WHEREVER REQUIRED ON THE SITE.
- 17. IMMEDIATELY UPON DISCOVERING UNFORESEEN CIRCUMSTANCES POSING THE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT POLLUTION, THE CONTRACTOR SHALL IMPLEMENT APPROPRIATE MEASURES TO ADDRESS SAID CIRCUMSTANCES.

FILL MATERIALS

IF THE SITE WILL NEED TO HAVE FILL IMPORTED FROM AN OFF SITE LOCATION. THE RESPONSIBILITY FOR PERFORMING ENVIRONMENTAL DUE DILIGENCE AND THE DETERMINATION OF CLEAN FILL WILL RESIDE WITH THE OPERATOR.

CLEAN FILL: IS DEFINED AS UNCONTAMINATED, NON-WATER SOLUBLE, NON-DECOMPOSABLE. INERT. SOLID MATERIAL. THE TERM INCLUDES SOIL, ROCK, STONE, DREDGED MATERIAL, USED ASPHALT, AND BRICK, BLOCK OR CONCRETE FROM CONSTRUCTION AND DEMOLITION ACTIVITIES THAT IS SEPARATE FROM THER WASTE AND IS RECOGNIZABLE AS SUCH. THE TERM DOES NOT INCLUDE MATERIALS PLACED IN OR ON THE WATERS OF THE COMMONWEALTH UNLESS OTHERWISE AUTHORIZED. (THE TERM "USED ASPHALT" DOES NOT INCLUDE MILLED ASPHALT OR ASPHALT THAT HAS BEEN PROCESSED FOR RE-USE.)

NMENTAL DUE DILIGENCE: INVESTIGATIVE TECHNIQUES, INCLUDING, BUT NOT LIMITED TO, VISUAL PROPERTY INSPECTIONS, ELECTRONIC DATA BASE SEARCHES, REVIEW OF PROPERTY OWNERSHIP, REVIEW OF PROPERTY USE HISTORY, SANBORN MAPS, ENVIRONMENTAL QUESTIONNAIRES, TRANSACTION SCREENS, ANALYTICAL TESTING, ENVIRONMENTAL ASSESSMENTS OR AUDITS, ANALYTICAL TESTING IS NOT A REQUIRED PART OF DUE DILIGENCE UNLESS VISUAL INSPECTION AND/OR REVIEW OF THE PAST LAND USE OF THE PROPERTY INDICATES THAT THE FILL MAY HAVE BEEN SUBJECTED TO A SPILL OR RELEASE OF REGULATED SUBSTANCE. IF THE FILL MAY HAVE BEEN AFFECTED BY A SPILL OR RELEASE OF A REGULATED SUBSTANCE. IT MUST BE TESTED TO DETERMINE IF IT QUALIFIES AS CLEAN FILL. TESTING SHOULD BE

FILL MATERIAL THAT DOES NOT QUALIFY AS CLEAN FILL IS REGULATED FILL. REGULATED FILL IS WASTE AND MUST BE MANAGED IN ACCORDANCE WITH THE DEPARTMENT'S MUNICIPAL OR RESIDUAL WASTE REGULATIONS BASED ON 25 PA. CODE CHAPTERS 287 RESIDUAL WASTE MANAGEMENT OR 271 MUNICIPAL WASTE MANAGEMENT, WHICHEVER IS APPLICABLE.

PROJECT CONSTRUCTION WASTES

- 1. TREES CHIPPED AND REMOVED OFFSITE FOR MULCH.
- 2. ROCK WASTE ALL ROCKS THAT ARE SUITABLE FOR LANDSCAPING USES SHALL BE USED ON SITE OR AT ANOTHER FACILITY.
- 3. SOIL WASTE ALL EXCAVATED SOIL SHALL BE USED ON SITE, AS FILL MATERIAL WHERE POSSIBLE. ANY EXCESS MATERIAL NOT USED ON SITE MAY ONLY BE DISPOSED AT A FACILITY WITH A VALID EARTH DISTURBANCE AND NPDES PERMIT APPROVED AND WERE ALL BMPS ARE PROPERLY INSTALLED. ALL SEDIMENT REMOVED DURING MAINTENANCE AND CLEANING OF EROSION AND SEDIMENTATION CONTROLS DEVICES WILL BE INCORPORATED INTO THE FINE GRADING UPSTREAM FROM A SEDIMENT CONTROL DEVICE. EXCESS MATERIAL THAT IS REMOVED FROM EROSION AND SEDIMENTATION CONTROL MEASURES AND CANNOT BE INCORPORATED INTO THE FINE GRADING STABILIZATION SHALL BE REMOVED FROM THE SITE AND MAY ONLY BE DISPOSED AT A FACILITY WITH A VALID EARTH DISTURBANCE AND NPDES PERMIT APPROVAL AND WERE ALL BMPS ARE PROPERLY INSTALLED.
- 4. SEDIMENT REMOVAL FROM ALL SEDIMENT BMP'S TO BE RETURNED TO SITE UPSTREAM OF ALL PROPOSED BMP'S.
- ALL BUILDING MATERIAL AND WASTES MUST BE REMOVED FROM THE SITE AND RECYCLED IN ACCORDANCE WITH DEP'S SOLID WASTE REGULATIONS (25 PA CODE 260.1 ET SEQ., 271.1 ET SEQ., AND 287.1 ET SEQ.), AND/OR ANY ADDITIONAL LOCAL, STATE OR FEDERAL REGULATIONS. NO BUILDING MATERIALS (USED OR UNUSED) OR WASTE MATERIALS SHALL BE BURNED, BURIED, DUMPED OR DISCHARGED AT THE SITE.
- 6. CONCRETE WASHOUT WASTE SHALL BE REMOVED AND DISPOSED OF IN ACCORDANCE WITH ALL STATE AND JURISDICTIONAL REQUIREMENTS.

IT IS REQUIRED TO RECYCLE WASTE MATERIALS, WHEN FEASIBLE.

- PERFORMED IN ACCORDANCE WITH APPENDIX A OF THE DEPARTMENT'S POLICY "MANAGEMENT OF FILL".

E&S PLANNING AND DESIGN NOTES GENERALLY, THE PROPOSED BMPS WERE SELECTED TO:

- MINIMIZE THE EXTENT AND DURATION OF EARTH DISTURBANCE BY LIMITING THE CLEARING, GRUBBING, AND TOPSOIL STRIPPING TO AREAS IN EACH STAGE OF THE CONSTRUCTION SEQUENCE. GENERAL SITE CLEARING, GRUBBING AND TOPSOIL STRIPPING MAY NOT COMMENCE IN ANY STAGE OF THE PROJECT UNTIL THE E&S BMP'S SPECIFIED BY THE CONSTRUCTION SEQUENCE FOR THAT STAGE HAVE BEEN INSTALLED AND ARE FUNCTIONING AS DESCRIBED IN THE E&S PLAN. IMMEDIATELY AFTER EARTH DISTURBANCE ACTIVITIES CEASE, THE CONTRACTOR SHALL STABILIZE ALL AREAS DISTURBED
- MAXIMIZE THE PROTECTION OF EXISTING DRAINAGE FEATURES AND VEGETATION BY ONLY LIMITING DISTURBANCE TO BE PERMITTED IN ORDER TO PROVIDE ACCESS TO INSTALL REQUIRED E&S BMP'S. THE BMP'S MUST BE CONSTRUCTED, STABILIZED AND FUNCTIONAL BEFORE SITE DISTURBANCE BEGINS WITHIN THE TRIBUTARY AREA TO THE UPSTREAM BMP'S. ALL E&S BMP'S SHALL REMAIN FUNCTIONAL UNTIL ALL UPSTREAM TRIBUTARY AREAS HAVE BEEN PERMANENTLY STABILIZED. AT NO TIME WILL CONSTRUCTION VEHICLES BE ALLOWED TO ENTER AREAS OUTSIDE THE LIMIT OF DISTURBANCE BOUNDARY. SEDIMENT TRACKED ONTO ANY PUBLIC ROADWAYS SHALL BE RETURNED TO THE CONSTRUCTION SITE BY THE END OF EACH WORK DAY. IN NO CASE SHALL THE SEDIMENT BE WASHED SHOVELED OR SWEPT INTO ANY ROADSIDE DITCH, STORM SEWER OR SURFACE WATER. ALL GRADED AREAS SHALL BE PERMANENTLY STABILIZED IMMEDIATELY UPON REACHING FINISHED GRADE THE PROPOSED DEVELOPMENT HAS BEEN DESIGNED TO MAINTAIN THE EXISTING DRAINAGE PATTERNS OF THE SITE.
- MINIMIZE SOIL COMPACTION BY IMPLEMENTING A SEQUENCE OF CONSTRUCTION THAT HAS BEEN DESIGNED TO LIMIT THE EXTENT AND DURATION OF DISTURBANCE ACTIVITIES THAT WILL LIMIT THE EXTENT OF HEAVY TRAFFIC OVER SENSITIVE AREAS NECESSARY FOR THE PCSM DESIGN.
- UTILIZE OTHER MEASURES OR CONTROLS THAT PREVENT OR MINIMIZE GENERATION OF INCREASED STORMWATER RUNOFF. THE PROPOSED DESIGN WILL DIRECT RUNOFF FROM THE CONSTRUCTION AREAS TO SPECIFIED E&S BMP'S (AS SHOWN ON THE EROSION AND SEDIMENT POLLUTION CONTROL PLAN) THAT WILL MITIGATE ANY STORMWATER RUNOFF PRIOR TO LEAVING THE SITE.

DMMERCIAL 10-20-10

SEEDING SPECIFICATIONS	
TEMPORARY:	

SPECIES	ANNUAL RYEGRASS
% PURE LIVE SEED	98%
APPLICATION RATE	87.0 LB/ACRE
FERTILIZER TYPE	COMMERCIAL 10-20-1
FERTILIZER APPL. RATE	1,100 LB/ACRE
LIMING RATE	2 T/ACRE
MULCH TYPE	STRAW
MULCH RATE	3 T/ACRE

BY ANY ACTIVITY.

PERMANENT: SPECIES

% PURE LIVE SEED APPLICATION RATE FERTILIZER TYPE

FERTILIZER APPL. RATE
LIMING RATE
MULCH TYPE
MULCH RATE
ANCHOR MATERIAL
ANCHORING METHOD
RATE OF ANCHOR MATERIAL AI
SEEDING SEASON DATES

FESCUE / PERENNIAL RYEGRASS / CHEWING'S RED FESCUE 41 / 20 / 14 / 20 LB/ACRE COMMERCIAL 10-20-10 1.100 LB/ACRE 2 T/ACRE HAY OR STRAW 3 T/ACRE HYDRO SEED WITH BONDED FIBER MATRIX DISK ROLLER SOPES <3:1, TACKIFYING AGENT ON SLOPES 3:1 OR GREATER APPL. PER MANUFACTURER SPECIFICATIONS

TOPSOIL APPLICATION NOTES

 GRADED AREAS SHOULD BE SCARIFIES OR OTHERWISE LOOSENED TO A DEPTH OF 3 TO 5 INCHES TO PERMIT BONDING OF THE TOPSOIL TO THE SURFACE AREAS AND TO PROVIDE A ROUGHENED SURFACE

APRIL 15 - MAY 30, AUGUST 15 - OCTOBER 15

KENTUCKY BLUEGRASS / SPREADING

- TO PREVENT TOPSOIL FROM SLIDING DOWN SLOPE TOPSOIL SHOULD BE UNIFORMLY DISTRIBUTED ACROSS THE DISTURBED AREAS TO A DEPTH OF 4 TO 8 INCHES MINIMUM - 2 INCHES ON FILL SLOPES. SPREADING SHOULD BE DONE IN SUCH A MANNER THAT SODDING OR SEEDING CAN PROCEED WITH A MINIMUM OF ADDITIONAL PREPARATION OF TILLAGE. IRREGULARITIES IN THE SURFACE RESULTING FROM TOPSOIL PLACEMENT SHOULD BE CORRECTED IN ORDER TO PREVENT FORMATION OF DEPRESSIONS UNLESS SUCH DEPRESSIONS ARE PART OF THE
- PCSM PLAN TOPSOIL SHOULD NOT BE PLACED WHILE THE TOPSOIL OR SUBSOIL IS IN A FROZEN OR MUDDY CONDITION, WHEN THE SUBSOIL IS EXCESSIVELY WET OR IN A CONDITION THAT MAY OTHERWISE BE DETRIMENTAL TO PROPER GRADING AND SEEDBED PREPARATION. COMPACTED SOILS SHOULD BE SCARIFIED 6 TO 12 INCHES ALONG THE CONTOUR WHEREVER POSSIBLE PRIOR TO SEEDING.

	TABLE 11.1	
DEPTH (IN)	PER 1,000 SQUARE FEET	PER ACRE
1	3.1	134
2	6.2	268
3	9.3	403
4	12.4	537
5	15.5	672
6	18.6	806
7	21.7	940
8	24.8	1074

FIELD EXPLORATION OF THE SITE SHALL BE MADE TO DETERMINE IF THERE IS SUFFICIENT SURFACE SOIL OF GOOD QUALITY TO JUSTIFY STRIPPING. TOPSOIL SHALL BE FRIABLE AND LOAMY (LOAM, SANDY LOAM, SILT LOAM, SANDY CLAY LOAM, CLAY LOAM). IT SHALL BE FREE OF DEBRIS, TRASH, STUMPS, ROCKS, ROOTS, AND NOXIOUS WEEDS, AND SHALL GIVE EVIDENCE OF BEING ABLE TO SUPPORT HEALTHY VEGETATION. IT SHALL CONTAIN NO SUBSTANCE THAT IS POTENTIALLY TOXIC TO PLANT GROWTH.

- ALL TOPSOIL SHALL BE TESTED BY A RECOGNIZED LABORATORY FOR THE FOLLOWING CRITERIA:
- ORGANIC MATTER CONTENT SHALL BE NOT LESS THAN 1.5% BY WEIGHT PH RANGE SHALL BE FROM 6.0 - 7.5. IF PH IS LESS THAN 6.0, LIME SHALL BE ADDED IN ACCORDANCE
- WITH SOIL TEST RESULTS OR IN ACCORDANCE WITH THE RECOMMENDATIONS OF THE VEGETATIVE ESTABLISHMENT PRACTICE BEING USED.
- SOLUBLE SALTS SHALL NOT EXCEED 500 PPM. IF ADDITIONAL OFF-SITE TOPSOIL IS NEEDED. IT MUST MEET THE STANDARDS STATED ABOVE.

GC TO TEST SOIL PRIOR TO TOPSOIL REDISTRIBUTION.

SOIL LIMITATIONS AND RESOLUTIONS

. <u>SEASONAL HIGH WATER TABLE LIMITATION</u> - DURING CONSTRUCTION PONDING WATER NEEDS TO BE PUMPED TO A SEDIMENT FILTER BAG OR OTHER SEDIMENT CONTROL BMP.

- 2. BEDROCK LIMITATION INFORM CONTRACTOR
- 3. CUTBANKS CAVE GC TO USE CAUTION WHEN TRENCHING. ALL APPLICABLE OSHA STANDARDS AND REGULATIONS MUST BE IMPLEMENTED AT ALL TIMES.
- 4. <u>CORROSIVE TO CONC./STEEL</u> GC TO PROVIDE TREATMENT TO ALL MATERIALS TO PREVENT CORROSION. (INCLUDING BUT NOT LIMITED TO: PAINTS, TARS, ETC..)
- 5. <u>EASILY ERODIBLE</u> PROVIDE TEMPORARY/PERMANENT STABILIZATION MEASURES AS NEEDED.
- 6. HYDRIC UTILIZE PUMPED WATER FILTER BAG WHEN WET SOILS ARE ENCOUNTERED. 7. LOW STRENGTH/LANDSLIDE PRONE - GC TO PROVIDE EROSION CONTROL MATTING ON SLOPES
- GREATER THAN 3:1 AND TAKE PRECAUTION TO AVOID OVERLOADING THE SOILS. 8. <u>SLOW PERCOLATION</u> - GC TO FENCE OFF INFILTRATION AREAS TO AVOID EXCESSIVE COMPACTION
- URING CONSTRUCTION. 9. PIPING - GC TO PROVIDE SUMP PUMP OR INSTALL UNDERDRAIN TO CONVEY PIPING FLOWS TO A BMP. 10. POOR SOURCE OF TOPSOIL - GC TO PROVIDE TOPSOIL AS NEEDED.
- 11. FROST ACTION WHEN SOILS WARRANT, PROVIDE UNDERDRAIN TO REMOVE EXCESSIVE WATER. 12. SHRINK/SWELL - CONTRECTOR TO IMPORT/EXPORT MATERIAL AS NEEDED. REFER TO ALL
- REGULATIONS FOR CLEAN FILL AND EXPORT REQUIREMENTS. 13. WETNESS - WHEN WET SOILS ARE ENCOUNTERED UTILIZE PUMPED WATER FILTER BAG TO DEWATER.

STAGE I - SEQUENCE OF CONSTRUCTION

ALL EARTH DISTURBANCE ACTIVITIES SHALL PROCEED IN ACCORDANCE WITH THE FOLLOWING SEQUENCE EACH STAGE SHALL BE COMPLETED IN COMPLIANCE WITH CHAPTER 102 REGULATIONS BEFORE ANY FOLLOWING STAGE IS INITIATED. CLEARING AND GRUBBING SHALL BE LIMITED ONLY TO THOSE AREAS DESCRIBED IN EACH STAGE.

AT LEAST SEVEN (7) DAYS BEFORE STARTING ANY EARTH DISTURBANCE ACTIVITIES, THE OPERATOR SHALL CONTACT ALL CONTRACTORS INVOLVED IN THOSE ACTIVITIES, THE LANDOWNER, ALL APPROPRIATE MUNICIPAL OFFICIALS, THE EROSION AND SEDIMENTATION CONTROL PLAN PREPARER, AND A REPRESENTATIVE OF THE MONTGOMERY COUNTY CONSERVATION DISTRICT TO SCHEDULE AN ON-SITE PRE-CONSTRUCTION MEETING. ALSO, AT LEAST THREE (3) DAYS BEFORE STARTING ANY EARTH DISTURBANCE ACTIVITIES, ALL CONTRACTORS INVOLVED IN THOSE ACTIVITIES SHALL NOTIFY THE PENNSYLVANIA ONE CALL SYSTEM INC. AT 1-800-242-1776 FOR BURIED UTILITIES LOCATION.

BEFORE IMPLEMENTING ANY REVISIONS TO THE APPROVED EROSION AND SEDIMENT CONTROL PLAN OR REVISIONS TO OTHER PLANS WHICH MAY AFFECT THE EFFECTIVENESS OF THE APPROVED E&S CONTROL PLAN, THE OPERATOR MUST RECEIVE APPROVAL OF THE REVISIONS FROM THE MONTGOMERY COUNTY CONSERVATION DISTRICT.

THE OPERATOR SHALL REMOVE FROM THE SITE, RECYCLE OR DISPOSE OF ALL BUILDING MATERIALS AND WASTES IN ACCORDANCE WITH THE DEPARTMENT'S SOLID WASTE MANAGEMENT REGULATIONS AT 25 PA CODE 260.1 ET SEQ., 271.1 E. SEQ. AND 287.1 ET SEQ.

BEFORE DISPOSING OF SOIL OR RECEIVING BORROW FOR THE SITE, THE OPERATOR MUST ASSURE THAT EACH SPOIL OR BORROW AREA HAS AN EROSION AND SEDIMENT CONTROL PLAN APPROVED BY THE MONTGOMERY COUNTY CONSERVATION DISTRICT, AND WHICH IS BEING IMPLEMENTED AND MAINTAINED ACCORDING TO CHAPTER 102 REGULATIONS.

STAGE I

- FENCING AND/OR PAINT.
- 2. INSTALL THE FOLLOWING EROSION AND SEDIMENT POLLUTION CONTROL BMP'S AS SHOWN ON THE - MOBILIZE AND CONSTRUCT STAGING AREA.
- INSTALL THE PROPOSED PERIMETER BMP'S. INSTALL ROCK CONSTRUCTION ENTRANCE AND CONCRETE WASHOUT. TEMPORARY STOCKPILES.
- INSTALL TREE PROTECTION FENCE.
- WATER MAINS.
- CONDITIONS AND DEMOLITION PLAN). AREA MUST BE PUMPED THROUGH A FILTER BAG. AS SOON AS SLOPES AND OTHER DISTURBED AREAS REACH FINAL GRADE THEY MUST BE
- RECOMMENDED.

STAGE II - SEQUENCE OF CONSTRUCTION

ALL EARTH DISTURBANCE ACTIVITIES SHALL PROCEED IN ACCORDANCE WITH THE FOLLOWING SEQUENCE. EACH STAGE SHALL BE COMPLETED IN COMPLIANCE WITH CHAPTER 102 REGULATIONS BEFORE ANY FOLLOWING STAGE IS INITIATED. CLEARING AND GRUBBING SHALL BE LIMITED ONLY TO THOSE AREAS DESCRIBED IN EACH STAGE.

FOR BURIED UTILITIES LOCATION.

BEFORE IMPLEMENTING ANY REVISIONS TO THE APPROVED EROSION AND SEDIMENT CONTROL PLAN OR REVISIONS TO OTHER PLANS WHICH MAY AFFECT THE EFFECTIVENESS OF THE APPROVED E&S CONTROL PLAN, THE OPERATOR MUST RECEIVE APPROVAL OF THE REVISIONS FROM THE MONTGOMERY COUNTY CONSERVATION DISTRICT

THE OPERATOR SHALL REMOVE FROM THE SITE. RECYCLE OR DISPOSE OF ALL BUILDING MATERIALS AND WASTES IN ACCORDANCE WITH THE DEPARTMENT'S SOLID WASTE MANAGEMENT REGULATIONS AT 25 PA CODE 260 1 FT SEQ 271 1 F SEQ AND 287 1 FT SEQ

CHAPTER 102 REGULATIONS.

STAGE II

- GENERAL NOTES) AND INSTALL EROSION CONTROL MATTING WHERE SHOWN AS PER DETAILS AND MANUFACTURES SPECIFICATIONS.
- BMP'S ONCE BUILDING ROOF ROOF HAS BEEN CONSTRUCTED, CONNECT ROOF DRAINS INTO SPECIFIED STORM SEWERS
- 3. INSTALL REMAINING STORM SEWERS AS SHOWN ON THIS PLAN. CONSTRUCT NEW STORM SEWERS FROM DOWN STREAM TO UPSTREAM. TRENCH ONLY AS FAR IN ONE DAY AS PIPE CAN BE INSTALLED IN THAT SAME PERIOD. PLACE SPOIL UPSLOPE OF THE TRENCH. BACKFILL TRENCH AND STABILIZE IMMEDIATELY.
- INSTALL INLET PROTECTION ONCE INSTALLATION HAS BEEN COMPLETED. 4. EXCAVATE AND INSTALL ALL REMAINING UTILITIES.
- 5. INSTALL CONCRETE CURBING.
- 6. INSTALL CARTWAY AND PARKING AREAS TO BINDER COURSE. - TOP COAT AND PAVEMENT MARKINGS DO NOT NEED TO BE INSTALLED AT THIS TIME.
- 7. INSTALL CONCRETE SIDEWALKS.
- 8. PERFORM FINAL GRADING. STABILIZE IMMEDIATELY. RESPREAD TOPSOIL SEED AREAS THAT ARE TO BE CONVERTED TO LAWN WITH PERMANENT MATERIAL REVEGETATE USING NATIVE SPECIES BMP
- 9. INSTALL WEARING COURSE WITHIN CARTWAY, PARKING AREAS AND DRIVEWAYS AND WITHIN THE RIGHT-OF-WAY - PAINT AND INSTALL ALL PROPOSED SIGNAGE.
- DISTURBANCE ASSOCIATED WITH SEDIMENT CONTROL REMOVAL
- CERTIFICATION STATEMENT FROM A LICENSED PROFESSIONAL.

THESE PLANS INDICATE CRITICAL AREAS FOR EROSION AND SEDIMENT CONTROL PLACEMENT BUT DO NOT RELIEVE THE CONTRACTOR FROM PROVIDING ADDITIONAL CONTROLS AS SITE CONDITIONS WARRANT. THE ENVIRONMENTAL COMPLIANCE MANAGER FOR THE PROJECT AND OR CONSERVATION DISTRICT MAY DIRECT THE CONTRACTOR TO INSTALL E&S BMPS NOT DEPICTED ON THESE DRAWINGS IN ORDER TO PROTECT DOWN GRADIENT AREAS FROM EROSION AND SEDIMENTATION DURING CONSTRUCTION

1. FIELD MARK LIMIT OF DISTURBANCE AS DEPICTED ON THIS PLAN USING TEMPORARY CONSTRUCTION

PERFORM INITIAL CLEARING AND GRUBBING WHICH SHALL BE LIMITED TO THE AREAS NEEDED TO

INSTALL COMPOST FILTER SOCKS #0-#[NUMBER]. PROVIDE IMMEDIATE STABILIZATION FOR

3. GC TO PERFORM UTILITY DIGS IN ORDER TO CONFIRM EXISTING DEPTHS/LOCATIONS PRIOR MAJOR EARTH DISTURBANCE ACTIVITIES, INCLUDING BUT NOT LIMITED TO EXISTING GAS, SEWER, STORM AND

4. STRIP SITE. DEMOLISH REMAINING ITEMS NOTED TO BE REMOVED. (REFERENCE C-02B - EXISTING OPERATOR SHALL REMOVE FROM SITE, RECYCLE OR DISPOSE OF ALL BUILDING MATERIAL AND WASTES IN ACCORDANCE WITH THE DEPARTMENT'S SOLID WASTE MANAGEMENT REGULATIONS AT 25 PA. CODE 260.1 ET SEQ., 271.1 ET SEQ. THE CONTRACTOR SHALL NOT ILLEGALLY BURY, DUMP OR DISCHARGE AND BUILDING MATERIAL OR WASTE AT THIS SITE. ANY WATER TRAPPED IN LOW LYING

STABILIZED. PROVIDE TEMPORARY STABILIZATION UPON COMPLETION OR TEMPORARY CESSATION OF ALL EARTH DISTURBANCE ACTIVITIES OF AT LEAST FOUR (4) DAYS. TO AVOID AIRBORNE PARTICLE ISSUES, DUST CONTROL MEASURES SHOULD BE ENACTED. SPRINKLING AND IRRIGATION IS

AT LEAST SEVEN (7) DAYS BEFORE STARTING ANY EARTH DISTURBANCE ACTIVITIES, THE OPERATOR SHALL CONTACT ALL CONTRACTORS INVOLVED IN THOSE ACTIVITIES THE LANDOWNER ALL APPROPRIATE MUNICIPAL OFFICIALS, THE EROSION AND SEDIMENTATION CONTROL PLAN PREPARER, AND A REPRESENTATIVE OF THE MONGOMERY COUNTY CONSERVATION DISTRICT TO SCHEDULE AN ON-SITE PRE-CONSTRUCTION MEETING. ALSO, AT LEAST THREE (3) DAYS BEFORE STARTING ANY EARTH DISTURBANCE ACTIVITIES, ALL CONTRACTORS INVOLVED IN THOSE ACTIVITIES SHALL NOTIFY THE PENNSYLVANIA ONE CALL SYSTEM INC. AT 1-800-242-1776

BEFORE DISPOSING OF SOIL OR RECEIVING BORROW FOR THE SITE, THE OPERATOR MUST ASSURE THAT EACH SPOIL OR BORROW AREA HAS AN EROSION AND SEDIMENT CONTROL PLAN APPROVED BY THE MONTGOMERY COUNTY CONSERVATION DISTRICT, AND WHICH IS BEING IMPLEMENTED AND MAINTAINED ACCORDING TO

1. ROUGH GRADE PROPOSED BUILDING PAD, DRIVE AISLES AND PARKING AREAS THROUGHOUT THE SITE AS SHOWN ON THE PLAN, PROVIDE TEMPORARY STABILIZATION (FOR TEMPORARY STABILIZATION REQUIREMENTS REFER TO GENERAL CONSERVATION NOTES AND SPECIFICATIONS ON SHEET C-01

2. COMMENCE BUILDING CONSTRUCTION. GC TO ENSURE POSITIVE DRAINAGE TO ALL SEDIMENT CONTROL

INSTALL FINAL VEGETATION INCLUDING SOD, LANDSCAPING AND TREES ASSOCIATED WITH THE FLUSH STORMSEWERS OF DEBRIS AND ALL UNWANTED MATERIALS.

10. UPON SITE STABILIZATION (ONCE ALL AREAS ARE COVERED WITH BUILDING FOUNDATIONS OR PAVEMENT. OR HAVE A STAND OF GRASS AT LEAST 70 PERCENT PERENNIAL/VEGETATIVE COVER. WITH A DENSITY CAPABLE OF RESISTING ACCELERATED EROSION AND SEDIMENTATION) AND BEFORE ANY TEMPORARY BMP'S ARE REMOVED, THE MONTGOMERY COUNTY CONSERVATION DISTRICT MUST BE NOTIFIED. UPON APPROVAL FROM THE MONTGOMERY COUNTY CONSERVATION DISTRICT, REMOVE ALL TEMPORARY EROSION AND SEDIMENT CONTROL FACILITIES AND DEMOBILIZE. IMMEDIATELY REPAIR AND STABILIZE ANY

11. CLEAR SITE OF ALL UNWANTED MATERIAL. OPERATOR SHALL REMOVE FROM SITE, RECYCLE OR DISPOSE OF ALL ONSITE MATERIAL AND WASTES IN ACCORDANCE WITH THE DEPARTMENT'S SOLID WASTE MANAGEMENT R, E, GULATIONS AT 25 PA. CODE 260.1 ET SEQ., 271.1 ET SEQ. THE CONTRACTOR SHALL NOT ILLEGALLY BURY, DUMP OR DISCHARGE AND BUILDING MATERIAL OR WASTE AT THIS SITE.

12. THE PERMITTEE SHALL INCLUDE WITH THE NOTICE OF TERMINATION "RECORD DRAWINGS": WITH A FINAL



112642001 08/30/2023

CALL BEFORE YOU DIG!


PENNSYLVANIA LAW REQUIRES 3 WORKING DAYS NOTICE FOR CONSTRUCTION PHASE AND 10 WORKING DAYS IN DESIGN STAGE – STOP CALL

🛞 PA 1

1-800-242-1776 SERIAL NUMBER: 20221403029 DATE REQUESTED: 05/20/2022

PRELIMINARY

NOT FOR CONSTRUCTION



TRAP. BERMS SHALL BE REQUIRED FOR ALL INSTALLATIONS. ROLLED EARTHEN BERM IN ROADWAY SHALL BE MAINTAINED UNTIL ROADWAY IS STONED. ROAD SUBBASE BERM ON ROADWAY SHALL BE MAINTAINED UNTIL ROADWAY IS PAVED. EARTHEN BERM IN CHANNEL SHALL BE MAINTAINED UNTIL PERMANENT STABILIZATION IS COMPLETED OR REMAIN PERMANENTLY.

2 IN X 2 IN. X 3/4 IN.

2:1 MAX.

6 IN.

MIN.

MOUNTABLE BERM (6 IN. MIN.)*

HEIGHT


AT A MINIMUM, THE FABRIC SHALL HAVE A MINIMUM GRAB TENSILE STRENGTH OF 120 LBS., A MINIMUM BURST STRENGTH OF 200 PSI, AND A MINIMUM TRAPEZOIDAL TEAR STRENGTH OF 50 LBS. FILTER BAGS SHALL BE CAPABLE OF TRAPPING ALL PARTICLES NOT PASSING A NO. 40 SIEVE.

INLET FILTER BAGS SHALL BE INSPECTED ON A WEEKLY BASIS AND AFTER EACH RUNOFF EVENT. BAGS SHALL BE EMPTIED AND RINSED OR REPLACED WHEN HALF FULL OR WHEN FLOW CAPACITY HAS BEEN REDUCED SO AS TO CAUSE FLOODING OR BYPASSING OF THE INLET. DAMAGED OR CLOGGED BAGS SHALL BE REPLACED. A SUPPLY SHALL BE MAINTAINED ON SITE FOR REPLACEMENT OF BAGS. ALL NEEDED REPAIRS SHALL BE INITIATED IMMEDIATELY AFTER THE INSPECTION. DISPOSE ACCUMULATED SEDIMENT AS WELL AS ALL USED BAGS ACCORDING

TO THE PLAN NOTES.

DO NOT USE ON MAJOR PAVED ROADWAYS WHERE PONDING MAY CAUSE TRAFFIC HAZARDS.

FILTER BAG INLET PREOTECTION - TYPE M INLET STANDARD CONSTRUCTION DETAIL #4-16 Scale: N.T.S



PROPER PIPE COVER AS SPECIFIED BY MANUFACTURER IS NOT OTHERWISE PROVIDED. PIPE

MAINTENANCE: ROCK CONSTRUCTION ENTRANCE THICKNESS SHALL BE CONSTANTLY MAINTAINED

TO THE SPECIFIED DIMENSIONS BY ADDING ROCK. A STOCKPILE SHALL BE MAINTAINED ON SITE

FOR THIS PURPOSE. ALL SEDIMENT DEPOSITED ON PAVED ROADWAYS SHALL BE REMOVED AND

RETURNED TO THE CONSTRUCTION SITE IMMEDIATELY. IF EXCESSIVE AMOUNTS OF SEDIMENT

ROADWAY OR SWEEPING THE DEPOSITS INTO ROADWAY DITCHES, SEWERS, CULVERTS, OR

ARE BEING DEPOSITED ON ROADWAY, EXTEND LENGTH OF ROCK CONSTRUCTION ENTRANCE BY

50 FOOT INCREMENTS UNTIL CONDITION IS ALLEVIATED OR INSTALL WASH RACK. WASHING THE

ROCK CONSTRUCTION ENTRANCE

STANDARD CONSTRUCTION DETAIL #3-1

SHALL BE SIZED APPROPRIATELY FOR SIZE OF DITCH BEING CROSSED.

OTHER DRAINAGE COURSES IS NOT ACCEPTABLE.

Scale: N.T.S.

RUNOFF SHALL BE DIVERTED FROM ROADWAY TO A SUITABLE SEDIMENT REMOVAL BMP PRIOR

TO ENTERING ROCK CONSTRUCTION ENTRANCE.

MOUNTABLE BERM SHALL BE INSTALLED WHEREVER OPTIONAL CULVERT PIPE IS USED AND


9

RIPRAP APRON AT PIPE OUTLET WITH ENDWALL STANDARD CONSTRUCTION DETAIL #9-1


ALL APRONS SHALL BE INSPECTED AT LEAST WEEKLY AND AFTER EACH RUNOFF EVENT. DISPLACED RIPRAP WITHIN THE APRON SHALL BE REPLACED IMMEDIATELY.


NOTES: ALL APRONS SHALL BE CONSTRUCTED TO THE DIMENSIONS SHOWN. TERMINAL WIDTHS SHALL BE ADJUSTED AS NECESSARY TO MATCH RECEIVING CHANNELS.

		RIPI	RAP	APRON		
OUTLET NO.	PIPE DIA Pd (IN)	SIZE R	THICK. Rt (IN)	LENGTH AI (FT)	INITIAL WIDTH Aiw (FT)	TERMINA L WIDTH Atw (FT)
RA-1	24	R-3	9	12	6	18
RA-2	24	R-3	9	12	6	18
RA-3	18	R-3	9	8	4.5	12.5
RA-4	18	R-4	18	10	4.5	14.5



SECTION Y-Y





Scale: N.T.S

STANDARD CONSTRUCTION DETAIL #4-1


COMPOST FILTER SOCK


BIODEGRADABLE COMPOST FILTER SOCKS SHALL BE REPLACED AFTER 6 MONTHS; PHOTODEGRADABLE SOCKS AFTER 1 YEAR. POLYPROPYLENE SOCKS SHALL BE REPLACED ACCORDING TO MANUFACTURER'S RECOMMENDATIONS. UPON STABILIZATION OF THE AREA TRIBUTARY TO THE SOCK, STAKES SHALL BE REMOVED. THE SOCK MAY BE LEFT IN PLACE AND VEGETATED OR REMOVED. IN THE LATTER CASE, THE MESH SHALL BE CUT OPEN AND THE MULCH SPREAD AS A SOIL SUPPLEMENT.

TRAFFIC SHALL NOT BE PERMITTED TO CROSS COMPOST FILTER SOCKS. ACCUMULATED SEDIMENT SHALL BE REMOVED WHEN IT REACHES 1/2 THE ABOVE GROUND HEIGHT OF THE BARRIER AND DISPOSED IN THE MANNER DESCRIBED ELSEWHERE IN THE PLAN. COMPOST FILTER SOCKS SHALL BE INSPECTED WEEKLY AND AFTER EACH RUNOFF EVENT. DAMAGED SOCKS SHALL BE REPAIRED ACCORDING TO MANUFACTURER'S SPECIFICATIONS OR REPLACED WITHIN 24 HOURS OF INSPECTION.

COMPOST FILTER SOCK SHALL BE PLACED AT EXISTING LEVEL GRADE. BOTH ENDS OF THE BARRIER SHALL BE EXTENDED AT LEAST 8 FEET UP SLOPE AT 45 DEGREES TO THE MAIN BARRIER ALIGNMENT. MAXIMUM SLOPE LENGTH ABOVE ANY BARRIER SHALL NOT EXCEED THAT SPECIFIED FOR THE SIZE OF THE SOCK AND THE SLOPE OF ITS TRIBUTARY AREA.

CENTER <u>PLAN VIEW</u> <u>NOTES:</u> SOCK FABRIC SHALL MEET STANDARDS OF TABLE 4.1 OF THE PA DEP EROSION CONTROL MANUAL. COMPOST SHALL MEET THE STANDARDS OF TABLE 4.2 OF THE PA DEP EROSION CONTROL MANUAL.













Scale: N.T.S.





				F	RISER				BARI	REL		EMBAN	KMENT	CLEAN	воттом
TRAP NO.	Z1 (FT)	Z2 (FT)	MAT'L		CREST ELEV RCE (FT)	BOT PERF ELEV (FT)	MAT'L	DIA Bd (IN)	INLET ELEV BIE (FT)	LENGT H BI (FT)	OUTLET ELEV BOE (FT)	TOP ELEV ETE (FT)	TOP WIDTH Etw (FT)	OUT ELEV COE (FT)	ELEV BE (FT)
1	3	3	CMP	24	143.60	143.00	RCP	24	138.00	24	137.35	145.00	10	143.00	142.00

		CONC	RETE B	ASE		OUTLET BASIN				
	TRAP NO.	LENGTH CBI (IN)	WIDT H CBw (IN)	THICK. CBt (IN)	RIPRAP SIZE (R)	ROCK THICK Rt (IN)	DEPTH D (IN)	WIDTH OBW (FT)	LENGTH OBL (FT)	
ĺ	1	4	4	0.275	R-3	9	N/A	20	14	

NOTES:

SEE DETAIL #8-3 TEMPORARY RISER FOR DETAILS OF THE TEMPORARY RISER CONSTRUCTION.

FILL MATERIAL FOR THE EMBANKMENTS SHALL BE FREE OF ROOTS, OR OTHER WOODY VEGETATION, ORGANIC MATERIAL, LARGE STONES, AND OTHER OBJECTIONABLE MATERIALS. THE EMBANKMENT SHALL BE COMPACTED IN LAYERED LIFTS OF NOT MORE THAN 6 TO 9 IN. THE MAXIMUM ROCK SIZE SHALL BE NO GREATER THAN 2/3 THE LIFT THICKNESS.

UPON COMPLETION, THE EMBANKMENT SHALL BE SEEDED AND MULCHED OR OTHERWISE STABILIZED ACCORDING TO THE SPECIFICATIONS OF THE E&S PLAN DRAWINGS.

ALL SEDIMENT TRAPS SHALL BE INSPECTED AT LEAST WEEKLY AND AFTER EACH RUNOFF EVENT.


ACCESS FOR SEDIMENT REMOVAL AND OTHER REQUIRED MAINTENANCE ACTIVITIES SHALL BE PROVIDED.

A CLEAN OUT STAKE SHALL BE PLACED NEAR THE CENTER OF EACH TRAP. ACCUMULATED SEDIMENT SHALL BE REMOVED WHEN IT HAS REACHED THE CLEAN OUT ELEVATION ON THE STAKE AND THE TRAP RESTORED TO ITS ORIGINAL DIMENSIONS. DISPOSE OF MATERIALS REMOVED FROM THE TRAP IN THE MANNER DESCRIBED IN THE E&S PLAN.

CHECK EMBANKMENTS, SPILLWAYS, AND OUTLETS FOR EROSION, PIPING AND SETTLEMENT. CLOGGED OR DAMAGED SPILLWAYS AND/OR EMBANKMENTS SHALL BE IMMEDIATELY RESTORED TO THE DESIGN SPECIFICATIONS. DISPLACED RIPRAP WITHIN THE OUTLET PROTECTION SHALL BE REPLACED IMMEDIATELY.

ACCUMULATED SEDIMENT SHALL BE REMOVED AND DISTURBED AREAS INSIDE THE TRAP SHALL BE STABILIZED BEFORE CONVERSION TO A STORMWATER MANAGEMENT FACILITY. TO ASSIST IN REMOVING SEDIMENT, WHICH MAY BE SATURATED, A DEVICE SUCH AS IS SHOWN IN STANDARD CONSTRUCTION DETAIL #7-18 MAY BE USED TO DEWATER THE SEDIMENT PRIOR TO ITS REMOVAL.





* SEE STANDARD CONSTRUCTION DETAIL #7-5, TRASH RACK AND ANTI-VORTEX DEVICE

** LOWEST HOLE AT SEDIMENT CLEAN-OUT ELEVATION

	Т	EMPORARY RISER			CON	BASE	BARREL	
TRAP NO.	DIA TRd (IN)	CREST ELEV TRCE (FT)	MAT'L	CLEAN OUT ELEV. COE (FT)	LENGTH CBI (IN)	WIDT H CBw (IN)	THICK. CBt (IN)	INLET ELEV BIE (FT)
1	24	143.60	CMP	143.00	4	4	0.275	138.00

A MINIMUM OF 2-#8 REBAR SHALL BE PLACED AT RIGHT ANGLES AND PROJECTING THROUGH SIDES OF RISER TO ANCHOR IT TO CONCRETE BASE. REBAR SHALL PROJECT A MINIMUM OF 1/4 RISER DIAMETER BEYOND OUTSIDE OF RISER.

CONCRETE BASE SHALL BE POURED IN SUCH A MANNER SO AS TO INSURE THAT CONCRETE FILLS BOTTOM OF RISER TO INVERT OF THE OUTLET PIPE TO PREVENT RISER FROM BREAKING AWAY FROM THE BASE. MINIMUM BASE WIDTH EQUALS 2 TIMES RISER DIAMETER.

EMBEDDED SECTION OF ALUMINUM OR ALUMINIZED PIPE SHALL BE PAINTED WITH ZINC CHROMATE OR EQUIVALENT.

CLOGGED OR DAMAGED SPILLWAYS SHALL BE REPAIRED IMMEDIATELY. TRASH AND OTHER DEBRIS SHALL BE REMOVED FROM THE BASIN AND RISER.


SEDIMENT TRAP TEMPORARY RISER

Scale: N.T.S.

2

<u>NOTES:</u>

STANDARD CONSTRUCTION DETAIL #8-3



4 IN. X 4 IN. PRESSURE TREATED -WOOD POSTS OR EQUIV. METAL


BASIN	BAF	TEMPO RISE	
or Trap No.	LENGTH Bal (FT)	HEIGHT Bah (FT)	CREST TRC (FT
1	125	1.60	143.
	TRAP	BASIN OR TRAP NO. (FT)	OR TRAP NO. LENGTH Bal (FT) HEIGHT Bah (FT)

NOTES:

SEE APPROPRIATE BASIN DETAIL FOR PROPER LOCATION AND ORIENTATION. RISER CREST. SUPER SILT FENCE BAFFLES NEED NOT EXTEND TO TRCE ELEVATION. CONSERVATION DISTRICT BEFORE INSTALLATION.


DAMAGED OR WARPED BAFFLES SHALL BE REPLACED WITHIN 7 DAYS OF INSPECTION.





- AN ACCEPTABLE ALTERNATIVE IS TO INSTALL A SUPER SILT FENCE AT THE BAFFLE LOCATION
- IN POOLS WITH DEPTHS EXCEEDING 7', THE TOP OF THE PLYWOOD BAFFLE DOES NOT NEED TO EXTEND TO THE TEMPORARY
- BAFFLES SHALL BE TIED INTO ONE SIDE OF THE BASIN UNLESS OTHERWISE SHOWN ON THE PLAN DRAWINGS.
- SUBSTITUTION OF MATERIALS NOT SPECIFIED IN THIS DETAIL SHALL BE APPROVED BY THE DEPARTMENT OR THE LOCAL
- BAFFLES REQUIRING SUPPORT POSTS SHALL NOT BE INSTALLED IN BASINS REQUIRING IMPERVIOUS LINERS.

STANDARD CONSTRUCTION DETAIL #7-14



Gresham

Smith

GreshamSmith.com


2222 Arlington Avenue South


Suite 202

Birmingham, AL 35205


Kimley **»Horn**


STRUCTURAL CIVIL GEOTECHNICAL







This Line is 3 Inches When Printed Full Size














GENERAL SEQUENCING NOTES FOR P.C.S.W.M. BMP'S 1. KIMLEY-HORN & ASSOCIATES, INC. SHALL BE NOTIFIED OF PRE-CONSTRUCTION MEETING DATE AND	P.C.S.W.M. B.M.P. INSPECTION AND MAINTENAM UNTIL THE SITE IS STABILIZED AND DURING THE CONSTRU
 THE CONSTRUCTION SCHEDULE. THE CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONS TO LIMIT THE COMPACTION IN THE 	MAINTAINED PROPERLY BY CONTRACTOR. ALL PERMANEN PERFORMED BY THE OWNER. MAINTENANCE MUST INCLUI
 PROPOSED BMP BOTTOMS. REFER TO THE BMP CONSTRUCTION DETAILS FOR CONSTRUCTION GUIDELINES OF ALL PROPOSED 	RUNOFF EVENT AND ON A WEEKLY BASIS. ALL PREVENTA INCLUDING CLEAN-OUT, REPAIR, REPLACEMENT, REGRAD MUST BE PERFORMED IMMEDIATELY AND IN ACCORDANCI
STORMWATER MANAGEMENT BMPS.	DETAILS. ANY AREAS DISTURBED DURING MAINTENANCE I ACCORDANCE WITH THE GENERAL CONSERVATION NOTE
4. A NOTICE OF TERMINATION (NOT) WILL BE REQUIRED TO BE SUBMITTED FOLLOWING ACCEPTANCE OF THE PROPOSED BMPS BY THE LICENSED PROFESSIONAL RESPONSIBLE FOR BMP INSTALLATION OVERSIGHT. PRIOR TO ACCEPTING THE NOT, THE DEPARTMENT AND/OR CONSERVATION DISTRICT STAFF WILL PERFORM A FINAL INSPECTION TO ENSURE SITE STABILIZATION AND VERIFY INSTALLATION AND FUNCTION OF STORMWATER BMPS.	MUST BE DOCUMENTED IN AN INSPECTION LOG KEPT FOR ACTIONS AND THE DATE, TIME AND NAME OF THE PERSON INSPECTION LOG MUST BE KEPT ON SITE AT ALL TIMES AN COUNTY CONSERVATION DISTRICT UPON REQUEST.
5. GENERALLY, THE PCSM BMP'S SHALL BE CONSTRUCTED IN THE FOLLOWING ORDER:	STORM CONVEYANCE SYSTEMS
- TO BE COMPLETED ONCE PCSM DESIGN IS ADVANCED	INSPECTION: STORM STRUCTURES AND PIPING SHALL E PROPER FUNCTIONALITY. REPAIR/REPLAC
P.C.S.W.M. STANDARD NOTES	MAINTENANCE: ALL ONSITE INLETS, MANHOLES, AND STOF EVERY THREE (3) MONTHS OR WHEN ACCU FACILITY. SYSTEMS SHALL BE FLUSHED E REMOVED FROM THE STORMWATER MANA
PERMIT TERMINATION UPON PERMANENT STABILIZATION OF THE EARTH DISTURBANCE ACTIVITY UNDER § 102.22(A)(2) (RELATING TO PERMANENT STABILIZATION), AND INSTALLATION OF BMPS IN ACCORDANCE WITH AN APPROVED PLAN PREPARED AND IMPLEMENTED IN ACCORDANCE WITH §§ 102.4 AND 102.8 (RELATING TO EROSION AND	LOCAL, STATE, AND FEDERAL STANDARDS LANDSCAPED AREAS, SOURCE OF EROSIC INLETS, MANHOLES, AND STORMWATER PI AND CLEARED IF ACCUMULATION OF SEDI
SEDIMENT CONTROL REQUIREMENTS; AND PCSM REQUIREMENTS), THE PERMITTEE OR CO-PERMITTEE SHALL SUBMIT A NOTICE OF TERMINATION TO THE DEPARTMENT OR CONSERVATION DISTRICT.	ANY BMP NOT DRAINING WITHIN 72 HOURS AFTER THE EN PCSM BMP FAILURE. BMP FAILURES INCLUDE BUT ARE NO
THE NOTICE OF TERMINATION MUST INCLUDE: (1) THE FACILITY NAME, ADDRESS AND LOCATION.	 POOR CONSTRUCTION TECHNIQUES, ESPECIALLY SOI SIGNIFICANTLY REDUCED INFILTRATION RATES.
 (2) THE OPERATOR NAME AND ADDRESS. (3) THE PERMIT NUMBER. (4) THE REASON FOR PERMIT TERMINATION. 	 A LACK OF SITE SOIL STABILIZATION PRIOR TO THE BI INCREASES THE POTENTIAL FOR SEDIMENT CLOGGIN
(5) IDENTIFICATION OF THE PERSONS WHO HAVE AGREED TO AND WILL BE RESPONSIBLE FOR LONG-TERM OPERATION AND MAINTENANCE OF THE PCSM BMPS IN ACCORDANCE WITH § 102.8(M) AND PROOF OF COMPLIANCE WITH § 102.8(M)(2).	 INADEQUATE PRETREATMENT, ESPECIALLY OF SEDIM GRADUAL REDUCTION OF INFILTRATION RATES. LACK OF PROPER MAINTENANCE (EROSION REPAIR, R BASIN CLEANING, VACUUMING OF PERVIOUS PAVEME OF BMP'S.
PCSM REQUIREMENTS PCSM REPORTING AND RECORDKEEPING. THE PCSM PLAN, INSPECTION REPORTS AND MONITORING RECORDS SHALL BE AVAILABLE FOR REVIEW AND INSPECTION BY THE DEPARTMENT OR THE CONSERVATION DISTRICT.	IT IS THE RESPONSIBILITY OF "THE RESPONSIBLE PARTY" OPERATIONS TO REMEDIATE THE PCSM BMP FAILURE IMM CONTACT A PROFESSIONAL ENGINEER TO DETERMINE TH
LICENSED PROFESSIONAL OVERSIGHT OF CRITICAL STAGES. A LICENSED PROFESSIONAL OR A DESIGNEE SHALL BE PRESENT ONSITE AND BE RESPONSIBLE DURING CRITICAL STAGES OF IMPLEMENTATION OF	CORRECTIVE ACTION MEASURE THAT CORRESPONDS TO MANUAL. IF IT IS DETERMINED BY THE MUNICIPAL ENGINE DISTRICT AND/OR PADEP THAT THE BMP'S ARE NOT FUNC
THE APPROVED PCSM PLAN. THE CRITICAL STAGES MAY INCLUDE THE INSTALLATION OF UNDERGROUND TREATMENT OR STORAGE BMPS, STRUCTURALLY ENGINEERED BMPS, OR OTHER BMPS AS DEEMED APPROPRIATE BY THE DEPARTMENT OR THE CONSERVATION DISTRICT.	DURING THE MAINTENANCE PERIOD, "THE RESPONSIBLE F REDESIGNING/MODIFYING THE BMP'S SO THAT THEY FUNC REQUIRED, THE BMP'S SHALL BE MONITORED FOR A MININ
FINAL CERTIFICATION. THE PERMITTEE SHALL INCLUDE WITH THE NOTICE OF TERMINATION "RECORD DRAWINGS" WITH A FINAL CERTIFICATION STATEMENT FROM A LICENSED PROFESSIONAL, WHICH READS AS FOLLOWS:	ARE COMPLETE AND WRITTEN CONFIRMATION SHALL BE O MONTGOMERY COUNTY CONSERVATION DISTRICT AND/OF WITHOUY FIRST OBTAINING WRITTEN PERMISSION FROM COUNTY CONSERVATION DISTRICT.
"I (NAME) DO HEREBY CERTIFY PURSUANT TO THE PENALTIES OF 18 PA.C.S.A. § 4904 TO THE BEST OF MY KNOWLEDGE, INFORMATION AND BELIEF, THAT THE ACCOMPANYING RECORD DRAWINGS ACCURATELY	
REFLECT THE AS-BUILT CONDITIONS, ARE TRUE AND CORRECT, AND ARE IN CONFORMANCE WITH CHAPTER 102 OF THE RULES AND REGULATIONS OF THE DEPARTMENT OF ENVIRONMENTAL PROTECTION AND THAT THE PROJECT SITE WAS CONSTRUCTED IN ACCORDANCE WITH THE APPROVED PCSM PLAN, ALL APPROVED PLAN CHANGES AND ACCEPTED CONSTRUCTION PRACTICES."	GEOLOGIC FORMATIONS THERE ARE KNOWN NATURALLY OCCURRING GEOLOGIC F WITHIN THE PROJECT LIMITS OF DISTURBANCE.
(1) THE PERMITTEE SHALL RETAIN A COPY OF THE RECORD DRAWINGS AS A PART OF THE APPROVED PCSM PLAN.	
(2) THE PERMITTEE SHALL PROVIDE A COPY OF THE RECORD DRAWINGS AS A PART OF THE APPROVED PCSM PLAN TO THE PERSON IDENTIFIED IN THIS SECTION AS BEING RESPONSIBLE FOR THE LONG-TERM OPERATION AND MAINTENANCE OF THE PCSM BMPS.	PROJECT CONSTRUCTION WASTE 1. TREES - CHIPPED AND REMOVED OFFSITE FOR MULCH.
PCSM LONG TERM OPERATIONS AND MAINTENANCE REQUIREMENTS	2. ROCK WASTE - ALL ROCKS THAT ARE SUITABLE FOR LA ANOTHER FACILITY.
JNTIL THE PERMITTEE OR CO-PERMITTEE HAS RECEIVED WRITTEN APPROVAL OF A NOTICE OF FERMINATION, THE PERMITTEE OR CO-PERMITTEE WILL REMAIN RESPONSIBLE FOR COMPLIANCE WITH	3. SOIL WASTE - ALL EXCAVATED SOIL SHALL BE USED ON EXCESS MATERIAL NOT USED ON SITE MAY ONLY BE DISP
THE PERMIT TERMS AND CONDITIONS INCLUDING LONG-TERM OPERATION AND MAINTENANCE OF ALL PCSM BMPS ON THE PROJECT SITE AND IS RESPONSIBLE FOR VIOLATIONS OCCURRING ON THE PROJECT SITE. THE DEPARTMENT OR CONSERVATION DISTRICT WILL CONDUCT A FINAL INSPECTION AND APPROVE	DISTURBANCE AND NPDES PERMIT APPROVED AND WERE SEDIMENT REMOVED DURING MAINTENANCE AND CLEANI
OR DENY THE NOTICE OF TERMINATION WITHIN 30 DAYS.	DEVICES WILL BE INCORPORATED INTO THE FINE GRADIN DEVICE. EXCESS MATERIAL THAT IS REMOVED FROM ERO AND CANNOT BE INCORPORATED INTO THE FINE GRADING
THE PERMITTEE OR CO-PERMITTEE SHALL BE RESPONSIBLE FOR LONG-TERM OPERATION AND MAINTENANCE OF PCSM BMPS UNLESS A DIFFERENT PERSON IS IDENTIFIED IN THE NOTICE OF TERMINATION AND HAS AGREED TO LONG-TERM OPERATION AND MAINTENANCE OF PCSM BMPS.	SITE AND MAY ONLY BE DISPOSED AT A FACILITY WITH A V APPROVAL AND WERE ALL BMPS ARE PROPERLY INSTALL
FOR ANY PROPERTY CONTAINING A PCSM BMP, THE PERMITTEE OR CO-PERMITTEE SHALL RECORD AN NSTRUMENT WITH THE RECORDER OF DEEDS WHICH WILL ASSURE DISCLOSURE OF THE PCSM BMP AND	4. SEDIMENT REMOVAL FROM ALL SEDIMENT BMP'S TO BE PROPOSED BMP'S.
THE RELATED OBLIGATIONS IN THE ORDINARY COURSE OF A TITLE SEARCH OF THE SUBJECT PROPERTY. THE RECORDED INSTRUMENT MUST IDENTIFY THE PCSM BMP, PROVIDE FOR NECESSARY ACCESS	5. ALL BUILDING MATERIAL AND WASTES MUST BE REMOV ACCORDANCE WITH DEP'S SOLID WASTE REGULATIONS (2
RELATED TO LONG-TERM OPERATION AND MAINTENANCE FOR PCSM BMPS AND PROVIDE NOTICE THAT THE RESPONSIBILITY FOR LONG-TERM OPERATION AND MAINTENANCE OF THE PCSM BMP IS A COVENANT THAT RUNS WITH THE LAND THAT IS BINDING UPON AND ENFORCEABLE BY SUBSEQUENT GRANTEES, AND PROVIDE PROOF OF FILING WITH THE NOTICE OF TERMINATION UNDER § 102.7(B)(5) (RELATING TO PERMIT TERMINATION	287.1 ET SEQ.), AND/OR ANY ADDITIONAL LOCAL, STATE O MATERIALS (USED OR UNUSED) OR WASTE MATERIALS SH DISCHARGED AT THE SITE.
THE PERSON RESPONSIBLE FOR PERFORMING LONG-TERM OPERATION AND MAINTENANCE MAY ENTER	6. CONCRETE WASHOUT WASTE SHALL BE REMOVED AND AND JURISDICTIONAL REQUIREMENTS.
ORGANIZATION, MUNICIPALITY, AUTHORITY, PRIVATE CORPORATION OR OTHER PERSON, TO TRANSFER THE RESPONSIBILITY FOR PCSM BMPS OR TO PERFORM LONG-TERM OPERATION AND MAINTENANCE AND PROVIDE NOTICE THEREOF TO THE DEPARTMENT.	7. IT IS REQUIRED TO RECYCLE WASTE MATERIALS, WHEN
A PERMITTEE OR CO-PERMITTEE THAT FAILS TO TRANSFER LONG-TERM OPERATION AND MAINTENANCE OF THE PCSM BMP OR OTHERWISE FAILS TO COMPLY WITH THIS REQUIREMENT SHALL REMAIN JOINTLY AND SEVERALLY RESPONSIBLE WITH THE LANDOWNER FOR LONG-TERM OPERATION AND MAINTENANCE OF THE PCSM BMPS LOCATED ON THE PROPERTY.	
FILL MATERIALS	STORMWATER BMP INSTALLATION OVERSIGHT
F THE SITE WILL NEED TO HAVE FILL IMPORTED FROM AN OFF SITE LOCATION, THE RESPONSIBILITY FOR PERFORMING ENVIRONMENTAL DUE DILIGENCE AND THE DETERMINATION OF CLEAN FILL WILL RESIDE WITH THE OPERATOR.	OF THE STORMWATER BMP'S (REFERENCE SEQUENCE OF TIMING).
<u>CLEAN FILL</u> : IS DEFINED AS UNCONTAMINATED, NON-WATER SOLUBLE, NON-DECOMPOSABLE, INERT, SOLID MATERIAL. THE TERM INCLUDES SOIL, ROCK, STONE, DREDGED MATERIAL, USED ASPHALT, AND BRICK,	TO BE COMPLETED ONCE PCSM DESIGN IS ADVANCE
MATERIAL. THE TERM INCLUDES SOIL, ROCK, STONE, DREDGED MATERIAL, USED ASPHALT, AND BRICK, BLOCK OR CONCRETE FROM CONSTRUCTION AND DEMOLITION ACTIVITIES THAT IS SEPARATE FROM OTHER WASTE AND IS RECOGNIZABLE AS SUCH. THE TERM DOES NOT INCLUDE MATERIALS PLACED IN OR ON THE WATERS OF THE COMMONWEALTH UNLESS OTHERWISE AUTHORIZED. (THE TERM "USED ASPHALT" DOES NOT INCLUDE MILLED ASPHALT OR ASPHALT THAT HAS BEEN PROCESSED FOR RE-USE.)	
ENVIRONMENTAL DUE DILIGENCE: INVESTIGATIVE TECHNIQUES, INCLUDING, BUT NOT LIMITED TO, VISUAL PROPERTY INSPECTIONS, ELECTRONIC DATA BASE SEARCHES, REVIEW OF PROPERTY OWNERSHIP,	
REVIEW OF PROPERTY USE HISTORY, SANBORN MAPS, ENVIRONMENTAL QUESTIONNAIRES, TRANSACTION SCREENS, ANALYTICAL TESTING, ENVIRONMENTAL ASSESSMENTS OR AUDITS. ANALYTICAL TESTING IS NOT	
A REQUIRED PART OF DUE DILIGENCE UNLESS VISUAL INSPECTION AND/OR REVIEW OF THE PAST LAND USE OF THE PROPERTY INDICATES THAT THE FILL MAY HAVE BEEN SUBJECTED TO A SPILL OR RELEASE OF REGULATED SUBSTANCE. IF THE FILL MAY HAVE BEEN AFFECTED BY A SPILL OR RELEASE OF A REGULATED SUBSTANCE, IT MUST BE TESTED TO DETERMINE IF IT QUALIFIES AS CLEAN FILL. TESTING SHOULD BE PERFORMED IN ACCORDANCE WITH APPENDIX A OF THE DEPARTMENT'S POLICY "MANAGEMENT OF FILL".	
FILL MATERIAL THAT DOES NOT QUALIFY AS CLEAN FILL IS REGULATED FILL. REGULATED FILL IS WASTE	

AND MUST BE MANAGED IN ACCORDANCE WITH THE DEPARTMENT'S MUNICIPAL OR RESIDUAL WASTE REGULATIONS BASED ON 25 PA. CODE CHAPTERS 287 RESIDUAL WASTE MANAGEMENT OR 271 MUNICIPAL WASTE MANAGEMENT, WHICHEVER IS APPLICABLE.

SEEDING SPECIFICATIONS

TEMPORARY: SPECIES ANNUAL RYEGRASS % PURE LIVE SEED 98% APPLICATION RATE 87.0 LB/ACRE FERTILIZER TYPE COMMERCIAL 10-20-10 FERTILIZER APPL. RATE 1,100 LB/ACRE I IMING RATE 2 T/ACRE MULCH TYPE STRAW MULCH RATE 3 T/ACRE

PERMANENT:

% PURE LIVE SEED APPLICATION RATE FERTILIZER TYPE FERTILIZER APPL. RATE LIMING RATE MULCH TYPE MULCH RATE ANCHOR MATERIAL ANCHORING METHOD SEEDING SEASON DATES

KENTUCKY BLUEGRASS / SPREADING FESCUE / PERENNIAL RYEGRASS / CHEWING'S RED FESCUE 41 / 20 / 14 / 20 LB/ACRE COMMERCIAL 10-20-10 1.100 LB/ACRE 2 T/ACRE HAY OR STRAW 3 T/ACRF HYDRO SEED WITH BONDED FIBER MATRIX DISK ROLLER SOPES <3:1, TACKIFYING AGENT ON SLOPES 3:1 OR GREATER RATE OF ANCHOR MATERIAL APPL. PER MANUFACTURER SPECIFICATIONS APRIL 15 - MAY 30, AUGUST 15 - OCTOBER 15

IAINTAINED PROPERLY BY CONTRACTOR. ALL PERMANENT MAINTENANCE PROCEDURES SHALL BE ERFORMED BY THE OWNER, MAINTENANCE MUST INCLUDE INSPECTIONS OF ALL BMPS AFTER EACH UNOFF EVENT AND ON A WEEKLY BASIS. ALL PREVENTATIVE AND REMEDIAL MAINTENANCE WORK. ICLUDING CLEAN-OUT, REPAIR, REPLACEMENT, REGRADING, RESEEDING, REMULCHING AND RENETTING UST BE PERFORMED IMMEDIATELY AND IN ACCORDANCE WITH THESE PROCEDURES, PLANS, AND ETAILS. ANY AREAS DISTURBED DURING MAINTENANCE MUST BE STABILIZED IMMEDIATELY IN CCORDANCE WITH THE GENERAL CONSERVATION NOTES AND SPECIFICATIONS. ALL SITE INSPECTIONS. IUST BE DOCUMENTED IN AN INSPECTION LOG KEPT FOR THIS PURPOSE INDICATING THE COMPLIANCE CTIONS AND THE DATE, TIME AND NAME OF THE PERSON CONDUCTING THE INSPECTION. THE ISPECTION LOG MUST BE KEPT ON SITE AT ALL TIMES AND MADE AVAILABLE TO THE MONTGOMERY COUNTY CONSERVATION DISTRICT UPON REQUEST. TORM CONVEYANCE SYSTEMS ISPECTION: STORM STRUCTURES AND PIPING SHALL BE INSPECTED ANNUALLY FOR TO ENSURE

AINTENANCE: ALL ONSITE INLETS, MANHOLES, AND STORMWATER PIPING SHALL BE CLEARED OF DEBRIS EVERY THREE (3) MONTHS OR WHEN ACCUMULATION HINDERS OPERATION OF THE

> REMOVED FROM THE STORMWATER MANAGEMENT SYSTEM SHALL BE DISPOSED PER LOCAL, STATE, AND FEDERAL STANDARDS. SHOULD ONSITE EROSION OCCUR FROM THE LANDSCAPED AREAS, SOURCE OF EROSION SHALL BE IMMEDIATELY STABILIZED AND THE INLETS. MANHOLES, AND STORMWATER PIPING SHALL BE CHECKED FOR ACCUMULATION AND CLEARED IF ACCUMULATION OF SEDIMENT EXISTS.

NY BMP NOT DRAINING WITHIN 72 HOURS AFTER THE END OF A RAIN EVENT SHOULD BE CONSIDERED A CSM BMP FAILURE. BMP FAILURES INCLUDE BUT ARE NOT LIMITED TO THE FOLLOWING:

- POOR CONSTRUCTION TECHNIQUES, ESPECIALLY SOIL COMPACTION/SMEARING, WHICH RESULTS IN SIGNIFICANTLY REDUCED INFILTRATION RATES.
- A LACK OF SITE SOIL STABILIZATION PRIOR TO THE BMP RECEIVING RUNOFE WHICH GREATLY
- INCREASES THE POTENTIAL FOR SEDIMENT CLOGGING FROM CONTIGUOUS LAND SURFACES. INADEQUATE PRETREATMENT, ESPECIALLY OF SEDIMENT LADEN RUNOFF, WHICH CAN CAUSE A
- GRADUAL REDUCTION OF INFILTRATION RATES. LACK OF PROPER MAINTENANCE (EROSION REPAIR, RE-VEGETATION, REMOVAL OF DETRITUS, CATCH BASIN CLEANING, VACUUMING OF PERVIOUS PAVEMENT, ETC.) WHICH CAN REDUCE THE LONGEVITY OF BMP'S.

PERATIONS TO REMEDIATE THE PCSM BMP FAILURE IMMEDIATELY. THE RESPONSIBLE PARTY SHALL CONTACT A PROFESSIONAL ENGINEER TO DETERMINE THE CAUSE OF THE BMP FAILURE AND PROVIDE A ORRECTIVE ACTION MEASURE THAT CORRESPONDS TO PROTOCOL 2 OF THE STORMWATER BMP IANUAL. IF IT IS DETERMINED BY THE MUNICIPAL ENGINEER, MONTGOMERY COUNTY CONSERVATION ISTRICT AND/OR PADEP THAT THE BMP'S ARE NOT FUNCTIONING PROPERLY DURING CONSTRUCTION OR URING THE MAINTENANCE PERIOD, "THE RESPONSIBLE PARTY" WILL BE RESPONSIBLE FOR EDESIGNING/MODIFYING THE BMP'S SO THAT THEY FUNCTION PROPERLY. IF MODIFICATIONS ARE EQUIRED, THE BMP'S SHALL BE MONITORED FOR A MINIMUM OF ONE YEAR AFTER THESE MODIFICATIONS RE COMPLETE AND WRITTEN CONFIRMATION SHALL BE OBTAINED FROM THE MUNICIPALITY IONTGOMERY COUNTY CONSERVATION DISTRICT AND/OR PADEP. FINAL GRADING CANNOT BE REVISED VITHOUY FIRST OBTAINING WRITTEN PERMISSION FROM THE MUNICIPALITY AND/OR MONTGOMERY OUNTY CONSERVATION DISTRICT.

HERE ARE KNOWN NATURALLY OCCURRING GEOLOGIC FORMATIONS THAT MAY CAUSE POLLUTION VITHIN THE PROJECT LIMITS OF DISTURBANCE.

. ROCK WASTE - ALL ROCKS THAT ARE SUITABLE FOR LANDSCAPING USES SHALL BE USED ON SITE OR AT NOTHER FACILITY.

SOIL WASTE - ALL EXCAVATED SOIL SHALL BE USED ON SITE, AS FILL MATERIAL WHERE POSSIBLE. ANY EXCESS MATERIAL NOT USED ON SITE MAY ONLY BE DISPOSED AT A FACILITY WITH A VALID EARTH DISTURBANCE AND NPDES PERMIT APPROVED AND WERE ALL BMPS ARE PROPERLY INSTALLED. ALL EDIMENT REMOVED DURING MAINTENANCE AND CLEANING OF EROSION AND SEDIMENTATION CONTROLS EVICES WILL BE INCORPORATED INTO THE FINE GRADING UPSTREAM FROM A SEDIMENT CONTROL EVICE. EXCESS MATERIAL THAT IS REMOVED FROM EROSION AND SEDIMENTATION CONTROL MEASURES ND CANNOT BE INCORPORATED INTO THE FINE GRADING STABILIZATION SHALL BE REMOVED FROM THE SITE AND MAY ONLY BE DISPOSED AT A FACILITY WITH A VALID EARTH DISTURBANCE AND NPDES PERMIT APPROVAL AND WERE ALL BMPS ARE PROPERLY INSTALLED.

. SEDIMENT REMOVAL FROM ALL SEDIMENT BMP'S TO BE RETURNED TO SITE UPSTREAM OF ALL ROPOSED BMP'S.

ALL BUILDING MATERIAL AND WASTES MUST BE REMOVED FROM THE SITE AND RECYCLED IN CCORDANCE WITH DEP'S SOLID WASTE REGULATIONS (25 PA CODE 260.1 ET SEQ., 271.1 ET SEQ., AND 87.1 ET SEQ.), AND/OR ANY ADDITIONAL LOCAL, STATE OR FEDERAL REGULATIONS. NO BUILDING IATERIALS (USED OR UNUSED) OR WASTE MATERIALS SHALL BE BURNED, BURIED, DUMPED OR ISCHARGED AT THE SITE.

ND JURISDICTIONAL REQUIREMENTS

. IT IS REQUIRED TO RECYCLE WASTE MATERIALS, WHEN FEASIBLE.

STORMWATER BMP INSTALLATION OVERSIGHT & CRITICAL STAGES THE CONTRACTOR SHALL NOTIFY THE PROFESSIONAL RESPONSIBLE FOR THE PROPER IMPLEMENTATION OF THE STORMWATER BMP'S (REFERENCE SEQUENCE OF CONSTRUCTION FOR SITE SPECIFICS AND

TO BE COMPLETED ONCE PCSM DESIGN IS ADVANCED

.C.S.W.M. B.M.P. INSPECTION AND MAINTENANCE NOTES

NTIL THE SITE IS STABILIZED AND DURING THE CONSTRUCTION ACTIVITIES, ALL BMPS MUST BE

PROPER FUNCTIONALITY. REPAIR/REPLACE AS NEEDED.

FACILITY. SYSTEMS SHALL BE FLUSHED EVERY FIVE (5) YEARS. ALL SEDIMENT/DEBRIS/OIL

IS THE RESPONSIBILITY OF "THE RESPONSIBLE PARTY" FOR STORMWATER MAINTENANCE AND

CONCRETE WASHOUT WASTE SHALL BE REMOVED AND DISPOSED OF IN ACCORDANCE WITH ALL STATE

PCSM PLAN PLANNING AND DESIGN NOTES

THE STORM DRAINAGE SYSTEM HAS BEEN DESIGNED TO INTERCEPT RUNOFF AT TOPOGRAPHIC LOW POINTS AND AREAS OF SIGNIFICANT RUNOFF QUANTITIES AND CONVEY STORMWATER TO THE PROPOSED STORMWATER MANAGEMENT BMP FACILITIES.

THE PROPOSED STORMWATER MANAGEMENT PROGRAM DESCRIBED ABOVE HAS BEEN DESIGNED TO COMPLY WITH THE LOWER PROVIDENCE TOWNSHIP STORMWATER MANAGEMENT ORDINANCE, NPDES AND THE STORMWATER MANAGEMENT ACT OF 1978.

THE PCSM AND BMP APPROACH OF THIS DEVELOPMENT IS MEANT TO PREVENT ADVERSE STORMWATER IMPACTS AND PROVIDE THE NECESSARY TREATMENT OF RUNOFF CLOSE TO THE ORIGIN OF THE IMPACT. THE PRIMARY GOAL OF THIS DEVELOPMENT'S STORMWATER MANAGEMENT PROGRAM WAS TO MIMIC, AS BEST AS POSSIBLE, THE PRE-DEVELOPMENT SITE HYDROLOGY BY USING BOTH STRUCTURAL AND NON-STRUCTURAL BMP'S TO PREVENT OR MINIMIZE CHANGES IN STORMWATER RUNOFF

GENERALLY, THE PROPOSED BMP'S WERE SERE SELECTED TO: PRESERVE THE INTEGRITY OF THE DOWNSTREAM CHANNELS AND MAINTAIN AND PROTECT THE

- PHYSICAL, BIOLOGICAL AND CHEMICAL QUALITIES THROUGH MITIGATING ANY INCREASES IN STORMWATER RUNOFF VOLUME DUE TO THE PROPOSED DEVELOPMENT AND TREATING RUNOFF FOR WATER QUALITY PURPOSES PRIOR TO BEING DISCHARGED FROM THE SITE. PREVENT AN INCREASE IN RATE OF STORMWATER RUNOFF. THE PROPOSED STORMWATER MANAGEMENT DESIGN HAS REDUCED THE POST-DEVELOPMENT PEAK RATE FROM THE
- PRE-DEVELOPMENT CONDITIONS, AS REQUIRED BY THE LOWER PROVIDENCE TOWNSHIP STORMWATER MANAGEMENT ORDINANCE. TO THE GREATEST EXTENT FEASIBLE, MINIMIZE ANY INCREASE IN STORMWATER RUNOFF VOLUME BY
- IMPLEMENTING VOLUME REDUCING BMP'S TO MITIGATE ANY ADDITIONAL RUNOFF VOLUME ASSOCIATED WITH THE PROPOSED IMPROVEMENTS MINIMIZE IMPERVIOUS SURFACES AND BREAK UP OR DISCONNECT THE FLOW OF RUNOFF OVER
- IMPERVIOUS SURFACES. RUNOFF FROM IMPERVIOUS AREAS IS DIRECTED TO WATER QUALITY BMP'S IN ORDER TO PRE-TREAT RUNOFF PRIOR TO BEING DISCHARGED FROM THE SITE. THE SITE CONVEYS RUNOFF THROUGH A SERIES OF WATER QUALITY BMP'S IN ORDER TO MAXIMIZE PRE-TREATMENT OF RUNOFF AND FURTHER MITIGATE ANY IMPACT TO PEAK RATE AND VOLUME IN THE POST DEVELOPMENT CONDITIONS. MAXIMIZE THE PROTECTION OF EXISTING DRAINAGE FEATURES AND EXISTING VEGETATION. THE
- PROPOSED DEVELOPMENT HAS BEEN DESIGNED TO MAINTAIN THE EXISTING DRAINAGE PATTERNS OF THE SITE AND PRESERVE EXISTING VEGETATION WHERE FEASIBLE. MINIMIZE LAND CLEARING AND GRADING. THE PROPOSED DEVELOPMENT IS DESIGNED TO MINIMIZE THE SMALLEST AMOUNT OF LAND DISTURBANCE FEASIBLE FOR ALL CONSTRUCTION RELATED
- ACTIVITIES. MINIMIZE SOIL COMPACTION. THE SEQUENCE OF CONSTRUCTION HAS BEEN DESIGNED TO LIMIT THE EXTENT AND DURATION OF DISTURBANCE ACTIVITIES AND TO LIMIT THE EXTENT OF HEAVY TRAFFIC OVER SENSITIVE AREAS NECESSARY FOR THE PCSM DESIGN.
- THE PROPOSED STORMWATER MANAGEMENT DESIGN UTILIZES OTHER STRUCTURAL AND NON-STRUCTURAL BMP'S TO PREVENT OR MINIMIZE GENERATION OF INCREASED STORMWATER RUNOFF TO THE GREATEST EXTENT POSSIBLE GIVEN THE EXISTING SITE CONSTRAINTS/CHARACTERISTICS.

SOIL DISPOSITION - SEDIMENT REMOVED FROM BMP'S SHALL BE DISPOSED OF IN LANDSCAPE AREAS OUTSIDE OF STEEP SLOPES, WETLANDS, FLOODPLAINS OR DRAINAGE SWALES. SEDIMENT SHALL BE IMMEDIATELY STABILIZED OR PLACED IN SOIL STOCKPILES.

STAGE I - SEQUENCE OF CONSTRUCTION

ALL EARTH DISTURBANCE ACTIVITIES SHALL PROCEED IN ACCORDANCE WITH THE FOLLOWING SEQUENCE. EACH STAGE SHALL BE COMPLETED IN COMPLIANCE WITH CHAPTER 102 REGULATIONS BEFORE ANY FOLLOWING STAGE IS INITIATED. CLEARING AND GRUBBING SHALL BE LIMITED ONLY TO THOSE AREAS DESCRIBED IN EACH STAGE

AT LEAST SEVEN (7) DAYS BEFORE STARTING ANY EARTH DISTURBANCE ACTIVITIES, THE OPERATOR SHALL CONTACT ALL CONTRACTORS INVOLVED IN THOSE ACTIVITIES, THE LANDOWNER, ALL APPROPRIATE MUNICIPAL OFFICIALS. THE EROSION AND SEDIMENTATION CONTROL PLAN PREPARER, AND A REPRESENTATIVE OF THE MONTGOMERY COUNTY CONSERVATION DISTRICT TO SCHEDULE AN ON-SITE PRE-CONSTRUCTION MEETING. ALSO, AT LEAST THREE (3) DAYS BEFORE STARTING ANY EARTH DISTURBANCE ACTIVITIES, ALL CONTRACTORS INVOLVED IN THOSE ACTIVITIES SHALL NOTIFY THE PENNSYLVANIA ONE CALL SYSTEM INC. AT 1-800-242-1776 FOR BURIED UTILITIES LOCATION.

BEFORE IMPLEMENTING ANY REVISIONS TO THE APPROVED EROSION AND SEDIMENT CONTROL PLAN OR REVISIONS TO OTHER PLANS WHICH MAY AFFECT THE EFFECTIVENESS OF THE APPROVED E&S CONTROL PLAN, THE OPERATOR MUST RECEIVE APPROVAL OF THE REVISIONS FROM THE MONTGOMERY COUNTY CONSERVATION DISTRICT.

THE OPERATOR SHALL REMOVE FROM THE SITE, RECYCLE OR DISPOSE OF ALL BUILDING MATERIALS AND WASTES IN ACCORDANCE WITH THE DEPARTMENT'S SOLID WASTE MANAGEMENT REGULATIONS AT 25 PA CODE 260.1 ET SEQ., 271.1 E. SEQ. AND 287.1 ET SEQ.

BEFORE DISPOSING OF SOIL OR RECEIVING BORROW FOR THE SITE, THE OPERATOR MUST ASSURE THAT EACH SPOIL OR BORROW AREA HAS AN EROSION AND SEDIMENT CONTROL PLAN APPROVED BY THE MONTGOMERY COUNTY CONSERVATION DISTRICT, AND WHICH IS BEING IMPLEMENTED AND MAINTAINED ACCORDING TO CHAPTER 102 REGULATIONS.

<u>STAGE I</u>

- FENCING AND/OR PAINT
- PLAN: - MOBILIZE AND CONSTRUCT STAGING AREA.
- INSTALL THE PROPOSED PERIMETER BMP'S.
- INSTALL COMPOST FILTER SOCKS #0-#[NUMBER]. PROVIDE IMMEDIATE STABILIZATION FOR TEMPORARY STOCKPILES.
- INSTALL TREE PROTECTION FENCE.
- WATER MAINS.
- CONDITIONS AND DEMOLITION PLAN).
- AREA MUST BE PUMPED THROUGH A FILTER BAG.
- RECOMMENDED

STAGE II - SEQUENCE OF CONSTRUCTION

DESCRIBED IN EACH STAGE.

AT LEAST SEVEN (7) DAYS BEFORE STARTING ANY EARTH DISTURBANCE ACTIVITIES, THE OPERATOR SHALL CONTACT ALL CONTRACTORS INVOLVED IN THOSE ACTIVITIES, THE LANDOWNER, ALL APPROPRIATE MUNICIPAL OFFICIALS, THE EROSION AND SEDIMENTATION CONTROL PLAN PREPARER, AND A REPRESENTATIVE OF THE MONGOMERY COUNTY CONSERVATION DISTRICT TO SCHEDULE AN ON-SITE PRE-CONSTRUCTION MEETING. ALSO, AT LEAST THREE (3) DAYS BEFORE STARTING ANY EARTH DISTURBANCE ACTIVITIES, ALL CONTRACTORS INVOLVED IN THOSE ACTIVITIES SHALL NOTIFY THE PENNSYLVANIA ONE CALL SYSTEM INC. AT 1-800-242-1776 FOR BURIED UTILITIES LOCATION

CONSERVATION DISTRICT.

260.1 ET SEQ., 271.1 E. SEQ. AND 287.1 ET SEQ. CHAPTER 102 REGULATIONS

STAGE II

- MANUFACTURES SPECIFICATIONS.
- SEWERS.
- 3. INSTALL REMAINING STORM SEWERS AS SHOWN ON THIS PLAN. - CONSTRUCT NEW STORM SEWERS FROM DOWN STREAM TO UPSTREAM. INSTALL INLET PROTECTION ONCE INSTALLATION HAS BEEN COMPLETED.
- 4. EXCAVATE AND INSTALL ALL REMAINING UTILITIES.
- 5. INSTALL CONCRETE CURBING.
- 6. INSTALL CARTWAY AND PARKING AREAS TO BINDER COURSE.
- 7. INSTALL CONCRETE SIDEWALKS.
- 8. PERFORM FINAL GRADING. STABILIZE IMMEDIATELY. RESPREAD TOPSOIL
- REVEGETATE USING NATIVE SPECIES BMP. - FLUSH STORMSEWERS OF DEBRIS AND ALL UNWANTED MATERIALS.
- RIGHT-OF-WAY. - PAINT AND INSTALL ALL PROPOSED SIGNAGE.
- DISTURBANCE ASSOCIATED WITH SEDIMENT CONTROL REMOVAL.
- CERTIFICATION STATEMENT FROM A LICENSED PROFESSIONAL

1. FIELD MARK LIMIT OF DISTURBANCE AS DEPICTED ON THIS PLAN USING TEMPORARY CONSTRUCTION

2. INSTALL THE FOLLOWING EROSION AND SEDIMENT POLLUTION CONTROL BMP'S AS SHOWN ON THE

PERFORM INITIAL CLEARING AND GRUBBING WHICH SHALL BE LIMITED TO THE AREAS NEEDED TO INSTALL ROCK CONSTRUCTION ENTRANCE AND CONCRETE WASHOUT.

3. GC TO PERFORM UTILITY DIGS IN ORDER TO CONFIRM EXISTING DEPTHS/LOCATIONS PRIOR MAJOR EARTH DISTURBANCE ACTIVITIES, INCLUDING BUT NOT LIMITED TO EXISTING GAS, SEWER, STORM AND

4. STRIP SITE. DEMOLISH REMAINING ITEMS NOTED TO BE REMOVED. (REFERENCE C-02B - EXISTING OPERATOR SHALL REMOVE FROM SITE, RECYCLE OR DISPOSE OF ALL BUILDING MATERIAL AND WASTES IN ACCORDANCE WITH THE DEPARTMENT'S SOLID WASTE MANAGEMENT REGULATIONS AT 25 PA. CODE 260.1 ET SEQ., 271.1 ET SEQ. THE CONTRACTOR SHALL NOT ILLEGALLY BURY, DUMP OR DISCHARGE AND BUILDING MATERIAL OR WASTE AT THIS SITE. ANY WATER TRAPPED IN LOW LYING AS SOON AS SLOPES AND OTHER DISTURBED AREAS REACH FINAL GRADE THEY MUST BE

STABILIZED. PROVIDE TEMPORARY STABILIZATION UPON COMPLETION OR TEMPORARY CESSATION OF ALL EARTH DISTURBANCE ACTIVITIES OF AT LEAST FOUR (4) DAYS. TO AVOID AIRBORNE PARTICLE ISSUES, DUST CONTROL MEASURES SHOULD BE ENACTED. SPRINKLING AND IRRIGATION IS

ALL EARTH DISTURBANCE ACTIVITIES SHALL PROCEED IN ACCORDANCE WITH THE FOLLOWING SEQUENCE. EACH STAGE SHALL BE COMPLETED IN COMPLIANCE WITH CHAPTER 102 REGULATIONS BEFORE ANY FOLLOWING STAGE IS INITIATED. CLEARING AND GRUBBING SHALL BE LIMITED ONLY TO THOSE AREAS

BEFORE IMPLEMENTING ANY REVISIONS TO THE APPROVED EROSION AND SEDIMENT CONTROL PLAN OR REVISIONS TO OTHER PLANS WHICH MAY AFFECT THE EFFECTIVENESS OF THE APPROVED E&S CONTROL PLAN, THE OPERATOR MUST RECEIVE APPROVAL OF THE REVISIONS FROM THE MONTGOMERY COUNTY

THE OPERATOR SHALL REMOVE FROM THE SITE, RECYCLE OR DISPOSE OF ALL BUILDING MATERIALS AND WASTES IN ACCORDANCE WITH THE DEPARTMENT'S SOLID WASTE MANAGEMENT REGULATIONS AT 25 PA CODE

BEFORE DISPOSING OF SOIL OR RECEIVING BORROW FOR THE SITE, THE OPERATOR MUST ASSURE THAT EACH SPOIL OR BORROW AREA HAS AN EROSION AND SEDIMENT CONTROL PLAN APPROVED BY THE MONTGOMERY COUNTY CONSERVATION DISTRICT, AND WHICH IS BEING IMPLEMENTED AND MAINTAINED ACCORDING TO

1. ROUGH GRADE PROPOSED BUILDING PAD, DRIVE AISLES AND PARKING AREAS THROUGHOUT THE SITE AS SHOWN ON THE PLAN, PROVIDE TEMPORARY STABILIZATION (FOR TEMPORARY STABILIZATION REQUIREMENTS REFER TO GENERAL CONSERVATION NOTES AND SPECIFICATIONS ON SHEET C-01 -GENERAL NOTES) AND INSTALL EROSION CONTROL MATTING WHERE SHOWN AS PER DETAILS AND

2. COMMENCE BUILDING CONSTRUCTION. GC TO ENSURE POSITIVE DRAINAGE TO ALL SEDIMENT CONTROL - ONCE BUILDING ROOF ROOF HAS BEEN CONSTRUCTED, CONNECT ROOF DRAINS INTO SPECIFIED STORM

TRENCH ONLY AS FAR IN ONE DAY AS PIPE CAN BE INSTALLED IN THAT SAME PERIOD. PLACE SPOIL UPSLOPE OF THE TRENCH. BACKFILL TRENCH AND STABILIZE IMMEDIATELY.

- TOP COAT AND PAVEMENT MARKINGS DO NOT NEED TO BE INSTALLED AT THIS TIME.

SEED AREAS THAT ARE TO BE CONVERTED TO LAWN WITH PERMANENT MATERIAL INSTALL FINAL VEGETATION INCLUDING SOD, LANDSCAPING AND TREES ASSOCIATED WITH THE

9. INSTALL WEARING COURSE WITHIN CARTWAY, PARKING AREAS AND DRIVEWAYS AND WITHIN THE

10. UPON SITE STABILIZATION (ONCE ALL AREAS ARE COVERED WITH BUILDING FOUNDATIONS OR PAVEMENT, OR HAVE A STAND OF GRASS AT LEAST 70 PERCENT PERENNIAL/VEGETATIVE COVER, WITH A DENSITY CAPABLE OF RESISTING ACCELERATED EROSION AND SEDIMENTATION) AND BEFORE ANY TEMPORARY BMP'S ARE REMOVED, THE MONTGOMERY COUNTY CONSERVATION DISTRICT MUST BE NOTIFIED. UPON APPROVAL FROM THE MONTGOMERY COUNTY CONSERVATION DISTRICT, REMOVE ALL TEMPORARY EROSION AND SEDIMENT CONTROL FACILITIES AND DEMOBILIZE. IMMEDIATELY REPAIR AND STABILIZE ANY

11. CLEAR SITE OF ALL UNWANTED MATERIAL. OPERATOR SHALL REMOVE FROM SITE, RECYCLE OR DISPOSE OF ALL ONSITE MATERIAL AND WASTES IN ACCORDANCE WITH THE DEPARTMENT'S SOLID WASTE MANAGEMENT R, E, GULATIONS AT 25 PA. CODE 260.1 ET SEQ., 271.1 ET SEQ. THE CONTRACTOR SHALL NOT ILLEGALLY BURY, DUMP OR DISCHARGE AND BUILDING MATERIAL OR WASTE AT THIS SITE.

12. THE PERMITTEE SHALL INCLUDE WITH THE NOTICE OF TERMINATION "RECORD DRAWINGS": WITH A FINAL

Gresham Smith

GreshamSmith.com

2222 Arlington Avenue South Suite 202 Birmingham, AL 35205





CALL BEFORE YOU DIG! PENNSYLVANIA LAW REQUIRES 3 WORKING DAYS NOTICE FOR CONSTRUCTION PHASE AND 10 WORKING DAYS IN DESIGN STAGE – STOP CALL PA 1 1-800-242-1776 SERIAL NUMBER: 20221403029 DATE REQUESTED: 05/20/2022


PRELIMINARY NOT FOR CONSTRUCTION


08/30/2023 This Line is 3 Inches When Printed Full Size

112642001









OUTLET CONTROL STRUCTURE #1


Ę

		(05	5-1)		
BMP	ORIFICE SIZE (IN)	ORIFICE INVERT ELEVATION	OUTLET ELEVATION	OUTLET PIPE SIZE (IN)	GRATE ELEVATION
BASIN 1	14" W X 6" H	141.17	138.00	24	142.50

OUTLET CONTROL STRUCTURE #2

	(05-2)							
BMP	STEEL WEIR PLATE	WEIR ELEVATION	OUTLET ELEVATION	OUTLET PIPE SIZE (IN)	SOLID LID ELEVATION			
BASIN 2	4' WIDE	136.60	134.50	24	144.21			


OUTLET CONTROL STRUCTURE FRONT VIEW





This Line is 3 Inches When Printed Full Size


CALL BEFORE YOU DIG! PENNSYLVANIA LAW REQUIRES 3 WORKING DAYS NOTICE FOR CONSTRUCTION PHASE AND 10 WORKING DAYS IN DESIGN STAGE – STOP CALL WWWTHAI.NEX. 1-800-242-1776 SERIAL NUMBER: 20221403029 DATE REQUESTED: 05/20/2022




















SECTION A - A HORIZONTAL SCALE - 1"=30 VERTICAL SCALE - 1"=30 *BUILDING HEIGHT SHOWN AT MAXIMUM ELEVATION. REFER TO ARCHITECTURAL ELEVATIONS FOR ACTUAL BUILDING DETAIL.

180			ION HOSPITAL*	PROPOSED REHABILITA	
160					
	\DE	PROPOSED GRADE			
140					
120					
110					

SECTION B - B HORIZONTAL SCALE - 1"=30 VERTICAL SCALE - 1"=30 *BUILDING HEIGHT SHOWN AT MAXIMUM ELEVATION. REFER TO ARCHITECTURAL ELEVATIONS FOR ACTUAL BUILDING DETAIL.




			180
			160
	GRADE		
	IGNADE		140
			140
			120
			110
			110
5+	50	6+00	6+27



This Line is 3 Inches When Printed Full Size





Drawn By: JTL	Checked By: JTL
	J
	AD\PIan Sheets\C-08AB SITE SECTIONS.dw
	LD Layout:C-OBE September 22, 2023 12:32:26pm K:\PIT_DS\112642001 - EHC Norristown, PA\CAD\PIan Sheets\C-08AB SITE SECTIONS.dwg
	September 22, 2023 12:32:26pm K: \P
	Set:EHC Norristown LD Layout: C-08E
	Plotted By: Litvin, Jared Sheet Set: EHC Norristown




ENTRANCE PROFILE HORIZONTAL SCALE - 1"=20 VERTICAL SCALE - 1"=20

	Gresham Smith
	GreshamSmith.com 2222 Arlington Avenue South Suite 202 Birmingham, AL 35205
	Kimley »Horn
	STRUCTURAL CIVIL GEOTECHNICAL
	% 550e ®
	Encompass Health
160 140 120 110 3+50	ENCOMPASS HEALTH REHABILITATION HOSPITAL OF NORRISTONN PRELIMIARY/FINAL LAND DEVELOPMENT 2660 Audubon Road, Norristown, PA 19403
	Revision No. Date Description I I I
CALL BEFORE YOU DIG! PENNSYLVANIA LAW REQUIRES 3 WORKING DAYS NOTCE FOR CONSTRUCTION PHASE AND 10 WORKING DAYS IN DESIGN STACE – STOP CALL WWW PAL 1-800-242-1776 SERIAL, NUER: 20221403029 DATE REQUESTED: 05/20/2022	DRIVEWAY PROFILE
PRELIMINARY NOT FOR CONSTRUCTION	C-08E 112642001 08/30/2023 This Line is 3 Inches When Printed Full Size












This Line is 3 Inches When Printed Full Size


MINIMUM THRUST BLOCK





















PRESSURE (PSI)	BEND ANGLE	CONCRETE REQUIRED (CU YD)	STEEL STRAP SIZE	"R" STRAP RADIUS	ANCHOR BOLT DIAMETER "D" AND NUMBER REQUIRED PER STRAP	EMBEDMENT LENGTH
0 - 100	ALL	1.0	1/4" x 2 1/2"	3 5/8"	(2) 3/4"	24"
101 - 200	ALL	2.5	1/4" x 2 1/2"	3 5/8"	* (2) 1"	36"
0 - 100	ALL	2.0	3/8" x 3"	4 3/4"	* (2) 1"	36"
101 - 200	45°	3.0	3/8" x 3"	4 3/4"	* (2) 1"	36"
101 - 200	90°	4.0	3/8" x 3"	4 3/4"	(4) 1"	36"
0 - 100	ALL	4.5	1/2" x 3"	6 3/4"	(4) 1"	36"
101 - 200	45°	6.0	(2) 1/2" x 3"	6 3/4"	(4) 1"	36"
101 - 200	90°	8.5	(2) 1/2" x 3"	6 3/4"	(4) 1"	36"





NOT FOR CONSTRUCTION

08/30/2023

This Line is 3 Inches When Printed Full Size



Ę




TABLE 13.1 Maximum Spacing and Materials for Trench Plugs

Trench Slope (%)	Spacing L (FT)	Plug Material
< 5	1,000	* Clay, Bentonite, or Concrete Filled Sacks
5 - 15	500	* Clay, Bentonite, or Concrete Filled Sacks
15 - 25	300	* Clay, Bentonite, or Concrete Filled Sacks
25 - 35	200	* Clay, Bentonite, or Concrete Filled Sacks
35 - 100	100	* Clay, Bentonite, or Concrete Filled Sacks
> 100	50	Cement Filled Bags (Wetted) or Mortared Stone


*TOPSOIL MAY NOT BE USED TO FILL SACKS.


Impervious trench plugs are required for all stream, river, wetland, or other water body crossings.


363-2134-008 / March 31, 2012 / Page 291





		Greshams	hith
	2222 Arlington Avenue South Suite 202 Birmingham, AL 35205		
	ŀ	Kimley	»Horn
	嗡	STRUCTURAL	ENGINEERS, INC.
	88 550e ®		
	Encompass Health		
	ENCOMPASS HEALTH	REHABILITATION HOSPITAL OF NORRISTOWN	PRELIMINARY/FINAL LAND DEVELOPMENT 2660 Audubon Road, Norristown, PA 19403
	No.		sion Description
CALL BEFORE YOU DIG! PENNSYLVANIA LAW REQUIRES 3 WORKING DAYS NOTICE FOR CONSTRUCTION PHASE AND 10 WORKING DAYS IN DESIGN STAGE - STOP CALL WWITHIN INC. 1-S00-242-1776 SERIAL NUMBER: 20221403029 DATE REQUESTED: 05/20/2022	UTILITY DETAILS		
PRELIMINARY NOT FOR CONSTRUCTION	C-09F 112642001 08/30/2023		


















This Line is 3 Inches When Printed Full Size




PLANT SC	HEDUL	.E			of BARBER
TREES	CODE	QTY	BOTANICAL NAME	COMMON NAME	SIZE
	Ac	17	Abies concolor	White Fir	6` HT. MIN,
	Ar	10	Acer rubrum	Red Maple	2" Cal.
	Ce	6	Cercis canadensis	Eastern Redbud Multi-trunk	
	Gp	11	Ginkgo biloba 'Princeton Sentry'	Princeton Sentry Maidenhair Tree	2" Cal.
-0 ⁰⁰⁰⁰⁰ /	Ms	8	Magnolia virginiana	Sweetbay Magnolia	
00000000000000000000000000000000000000	Рс	25	Picea pungens	Colorado Spruce	6` HT. MIN,
•	Qr	9	Quercus rubra	Red Oak	2" Cal.
Justitution of the second seco	Tn	41	Thuja occidentalis 'Nigra'	Black Arborvitae	6` HT. MIN,
(•)	Zv	11	Zelkova serrata 'Village Green'	Village Green Japanese Zelkova	2" Cal.
SHRUBS	CODE	QTY	BOTANICAL NAME	COMMON NAME	SIZE
\bigcirc	Ak	66	Abelia chinensis `Keiser`	Ruby Anniversary® Chinese Abelia	1.5` Ht.
(+)	Bs	87	Buxus sempervirens	Common Boxwood	1.5` Ht.
\bigcirc	Cg	104	Cornus racemosa	Gray Dogwood	1.5` Ht.
2)	Jf	85	Juniperus chinensis `Sea Green`	Sea Green Juniper	1`Ht.
Correction of the second se	Vc	136	Viburnum carlesii	Koreanspice Viburnum	1.5` Ht.
GROUND COVERS	<u>QTY</u>	BOTANICAL NAME	COMMON NAME	DENSITY	
• اد اد اد اد اد اد اد اد اد ا	39,575 sf	GRASS SEED			
* × × × × × × × × × × × × × × × × × × ×	38,940 sf	Retention Basin Floor Mix	ERNMX-126		


This Line is 3 Inches When Printed Full Size



Ę



PLANT SC	HEDUL	.E				
TREES		QTY	BOTANICAL NAME	COMMON NAME	SIZE	CON
	Ac	17	Abies concolor	White Fir	6` HT. MIN,	B&B
	Ar	10	Acer rubrum	Red Maple	2" Cal.	B&B
	Ce	6	Cercis canadensis	Eastern Redbud Multi-trunk		
	Gp	11	Ginkgo biloba 'Princeton Sentry'	Princeton Sentry Maidenhair Tree	2" Cal.	B&B
	Ms	8	Magnolia virginiana	Sweetbay Magnolia		
80 ⁰⁰⁰⁰⁰⁰⁰⁰⁰⁰⁰⁰⁰⁰⁰⁰⁰⁰⁰⁰⁰⁰⁰⁰⁰⁰⁰⁰⁰⁰⁰⁰⁰⁰⁰	Рс	25	Picea pungens	Colorado Spruce	6` HT. MIN,	B&B
•	Qr	9	Quercus rubra	Red Oak	2" Cal.	B&B
yyyuuuuuu	Tn	41	Thuja occidentalis 'Nigra'	Black Arborvitae	6` HT. MIN,	B&B
	Zv	11	Zelkova serrata 'Village Green'	Village Green Japanese Zelkova	2" Cal.	B&B
SHRUBS	CODE	QTY	BOTANICAL NAME	COMMON NAME	SIZE	CON
\bigcirc	Ak	66	Abelia chinensis `Keiser`	Ruby Anniversary® Chinese Abelia	1.5` Ht.	# 3 C
(+)	Bs	87	Buxus sempervirens	Common Boxwood	1.5` Ht.	# 3 C
\bigcirc	Cg	104	Cornus racemosa	Gray Dogwood	1.5` Ht.	# 3 C
۲ ۲ ۲ ۲	Jf	85	Juniperus chinensis `Sea Green`	Sea Green Juniper	1`Ht.	# 3 C
6 . 5 . 5 . 5 . 5 . 5 . 5 . 5 . 5 . 5 . 5	Vc	136	Viburnum carlesii	Koreanspice Viburnum	1.5` Ht.	#5 C
GROUND COVERS	QTY	BOTANICAL NAME	COMMON NAME	DENSITY		
ا د د د د اد د د د د د د د	39,575 sf	GRASS SEED				



Drawn Bv

GENERAL NOTES

- 1. Plants shall be healthy, vigorous material, free of pests and diseases and are subject to approval/rejection of the Landscape Architect prior to, during and after installation.
- 2. Contractor shall identify all materials at growing location prior to purchase and submit digital photographs, and source list to the Landscape Architect for approval at a minimum of six (6) calendar weeks prior to installation. Plants not approved shall be resourced and resubmitted.
- 3. Planting beds and individual tree plantings shall be mulched continuously as specified.
- 4. Prior to construction the contractor shall be responsible for locating underground utilities and execute work in a manner that avoids damage to utilities during the course of work. Contractor shall be responsible or remedy of any damage to utilities, structures, site appurtenances that occur as a result of landscape related work. 5. Contractor is responsible for verifying quantities shown on documents. Field adjustments shall be
- approved by Landscape Architect prior to installation. Quantities indicated on drawings are for reference-it is the Contractor's responsibility to ensure full coverage of plants at the indicated spacing.
- 6. Contractor is responsible for maintenance of all plantings including, but not limited to watering, mowing. edging, spraying, mulching, fertilizing, of plantings and turf areas for one (1) calendar year from date of certificate of occupancy. Contractor is responsible for warranty of all plant material for a period of one (1) calendar year from date of certificate of occupancy. Warranty replacement planting shall meet or exceed the original specification identified on drawings. Replacement planting shall extend the same warranty as originally installed materials. Plantings and grass areas shall be flourishing and fully thriving at end of warranty period.
- 7. Plants identified for replacement by Owner, Landscape Architect shall be replaced immediately by the Contractor unless otherwise agreed upon. Plantings (trees, shrubs, groundcover) subject to replacement by warranty shall exhibit characteristics of 30% dead-per individual plant, non-contributing or disease compromised. Grass areas suitable for acceptance shall demonstrate 85% sustained/consistent and continuous, densely established coverage.
- Contractor shall perform a site review at end of warranty period and provide the Owner with written documentation of the site, including plant health, warranty replacement items, and conditions that may be influencing plant health. Contractor shall remove from plants and site, all staking and guying material at end of warranty period.
- 8. Contractor shall comply with all local, state and federal requirements, codes and regulations related to the work undertaken
- 9. All material including planting operation appurtenances shall be of domestic origin manufacture and sourced within 100 miles of the project site.
- 10. Contractor is responsible for coordination among trades operating on site. Coordination and if necessary resulting modifications to schedules are responsibility of the Contractor.

PERFORMANCE SPECIFICATION

I. PLANTS A.General

- 1. Live healthy plants free of dead branches and parts
- 2. Free of disease, insect, injury and damage
- 3. Unbroken, intact, dense and solid rootballs and containers, without cracks, flat sides or previously repaired damade
- 4. Free of girdling roots or rootbound/circling container conditions 5. Plants of consistent in growth habit and healthy character
- 6. Free of compromising growth conditions such as weak crotch connections, crossed branches, snags and
- 7. Point of origin growing location within 100 miles of project site 8. Graded, standards, caliper, sizes and stock consistent with ANSI Z60.1, American Standard for Nursery
- Stock most current edition 9. Species identified consistent with Hortus Third: Concise Dictionary of Plants Cultivated in the United States and Canada, most current edition and Manual of Woody Plants: Their Identification, Ornamental Characteristics, Culture, Propagation and Uses, most current edition
- 10. All disturbed areas shall be grass seed unless otherwise identified on landscape plans

B. Trees:

- 1. Deciduous Single Trunk
- a. Full, straight and upright with consistent symmetrical natural branching pattern throughout b. Branching Height-seven (7) feet to lowest branch in two years unless otherwise required by local jurisdiction

2. Deciduous Multi-Trunk

- a. Full and upright with straight consistent symmetrical natural branching pattern throughout b. Canes evenly spaced and of similar growth habit c. Free of suckers and extraneous branching
- 3. Evergreen Single-Trunk
- a. Full and upright with continuous symmetrical dense natural habit
- b. Clear branching height twelve (12) inches above top of rootball
- c. Free of suckers and extraneous branching d. Do not shear or otherwise prune to shape plantings
- C.Evergreen and Deciduous Shrubs
- 1. Full, dense and naturally symmetrical.
- 2. Consistent with container and/or balled and burlapped size
- 3. Free of suckers and extraneous branching 4. Do not shear or otherwise prune or shape plantings

D. Evergreen and Deciduous Groundcover 1. Full and dense in pots or flats

- **E. Perennials and Seasonal Color**
- 1. Full and dense in pots or flats

F. Turf Grass 1. Subgrade

- a. Soil Mix-10% Compost, 90% topsoil by volume
- b. Preparation-loosen subgrade to a minimum depth of four (4) inches. Remove all non-natural materials including litter, stones, sticks and all items greater than ³/₄ inch in any dimension c. Preparation-spread soil mix at a depth of four (4) inches continuously to meet grade elevations shown
- on drawings. Allow for thickness of sod when applicable

2. Grass Sod

- a. Install not longer than twenty-four (24) hours from harvest
- b. Grass bed not less than two (2) inches in continuous thickness
- c. 100% continuous live sod coverage after first growing season and at end of warranty period. d. Of uniform non-varying density and continuous texture quality capable of growth and development immediately upon installation. Weed and noxious plant free
- e. Stagger installation rows and place aligned parallel to contours
- f. Fill joints solidly with planting bed preparation soil
- 3. Grass Seed
- a. Mix approved by the Landscape Architect
- b. Provide first and new of year seed crops in mix free of weed seeds and deleterious matter c. Provide seed mix not greater than 15% annual or perennial rye
- d. Coverage 85% continuous coverage live stand after first growing season and at end of warranty
- e. Replacement or overseeding mixes consistent with original application/installation f. Provide erosion blankets or other slope retention methods as noted on drawings

g. Provide anchor pins at twenty-four (24) inches on center for slopes greater than 4:1

II. Materials and Appurtenances

A.Testing 1. Materials testing information/certificates/dated labels shall be current to the project and performed/certified not greater than 120 calendar previous days from current date of submittal for review

B. Top Soil

- I. Neutral Ph balance 5.5 -7.5. Friable and containing 2.0-5.0% organic matter by dry weight. Continuously free of non-soil items such as stones, debris, sticks, trash, and deleterious matter greater than 3/4 inch in any direction. Clay content shall not exceed 25%.Gravel content shall not exceed 10%. Silt shall not exceed 25%
- C.Use of Existing Topsoil
- 1. Existing topsoil on-site may be repurposed with prior Owner approval. Contractor shall provide soil testing and additive program that demonstrates consistent performance and characteristics and composition as identified herein. Owner shall approve soil testing and soil amendment/additive methods and procedures

D. Shredded Hardwood Mulch

Neutral Ph balance 5.5-7.5

- E. Compost Ph

G.Compost Testing

- requirements
- the US Composting Council Seal of Testing approval programs
- H.Planting Mix 1. 85% topsoil and 15% Compost

I. Fertilizer Product and Material Safety Data as approved by Owner

J. Herbicide

- 1. Product and Material Safety Data as approved by Owner K. Water
- 1. Potable only unless otherwise approved by Owner
- L. Hardwood Stakes 1. 2 x 2 x 48 inch square of sound hardwood, painted flat black on all sides

M.Tree Ties

- 1. Villa Non-Abrasive Rubber Tree Ties or approved equal
- N.Filter Fabric 1. Mirafi 140-N or approved equal

O.Steel Edging

P. River Stone

- 1. Locally sourced, river rounded, unfaceted river stone/cobbles. 2. Size shall not exceed 3 total inches in any dimension.
- 3. Color and texture approved by Owner
- 5. Concrete or mortar as approved by owner.

III. Execution A.Site Conditions

- of acceptance prior to commencement of work.
- 3. Notify Owner in writing of any conditions that may preclude successful completion of work including items
- access to storage/work areas, damage to conditions, etc. materials delivery and/or installation and warranty responsibilities.
- work by others.

B.Planting Seasons

Recommended seasons are a general guide based on historical climatic data and typical performance of plantings, and which vary dependent on project-specific environmental conditions. Due to construction schedules, recommended planting seasons may/may not coincide with request(s) for certificate of occupancy for projects. Coordination of planting installation and seasons shall be reviewed with Owner on an individual project basis.

1. Deciduous and Evergreen Trees Do not install/plant the following trees between September 15 and March 15 1. Oaks (Quercus Sp., Such as Q. rubra, Q. alba, Q. phellos, Q. coccinnea) 2. Dogwood (Cornus Sp.) 3. Sweetgum (Liquidambar Sp.)

2. Deciduous and Evergreen Shrubs

3. Perennials

- 4. Spring Flowering Bulbs a. Install/plant between September 15 and December 15
- Seasonal Annuals a. Install/plant in season per approved schedule
- 6. Turf Grass

C.Positioning & Location of Plantings

7. No Plant Installation

installation

Owner approval

D.Implementation

E. Clean Up

Architect.

furnishings, etc.

1. 100% organic shredded first year hardwood free of deleterious matter, rock, gravel and weed seed.

1. Balanced 5.0-8.5 mature, stable and weed free produced by natural aerobic decomposition. Free of visible contaminants and toxic substances. Not greater than 5% sand, silt, clay or rock by dry weight. Consistent with US-EPA CFR Title 40 Part 503 Standards for Class A biosolids

1. Prior to delivery on-site, the following items are required for approval by Owner: Feedstock percentage in final compost product; statement that the products meets federal, state and local health safety

2. Provide copy of lab analysis less than 120 calendar days old verifying that the product meets described physical requirements; chemical contaminants; Ph; physical contaminants; biological contaminants (including a statement that fecal coliform and salmonella testing and results comply with requirements of

1. Granular 10% nitrogen, 6% Phosphorous, 4% Potassium granular form with 50% Nitrogen in organic form.

1. 1/8-inch x 4-inch in full sections. Ryerson, Timec or approved equal with integral stakes. No open corners. Corners shall be formed and trued to compliant angle or welded closed

4. When placed in concrete or mortar setting bed, tamp to secure and brush clear joints

1. Inspect site and notify Owner in writing of acceptance with indication that project conditions are acceptable are suitable to proceed with work. Notify Owner of any existing damage and/or other conflicting conditions. 2. Do not proceed with work until unsatisfactory conditions have been satisfactorily remedied. Notify Owner

such as coordination with other trades, incomplete work, drainage, soil temperature and/or composition, 4. Notify Owner in writing immediately of any items that may influence work schedule, timing of tasks,

5. Coordinate and cooperate with other trades working in and adjacent to work areas. Examine drawings of other trades which show development of the entire project and become familiar with the scope of required

4. All Conifers and Evergreens except White Pine (Pinus strobus Sp.)

a. Install/plant between March 15 and June 15 and/or September 15 and November 30

a. Install/plant between March 15 and June 15 and/or September 15 and November 30

a. Install/plant between March 15 and May 15 and/or September 15 and November 30 b. Do not install/plant seed or sod turf grass areas when ambient air temperature is below forty (40) degrees Fahrenheit, or forecast for a twelve (12) hour period after completion of work

a. Do not install plantings or turf grass between June 15 and September 15, without approval by Owner

1. Position plants to show the most-prominent and well-formed face to most-public view

2. Field locate plants and location/spacing/dimension of planting beds on project site prior to beginning 3. Verify location of individual plants and plant beds prior to beginning installation. Do not proceed without

1. Pursue work continuously without delay or interruption until completion unless notified otherwise by Owner 2. Provide project submittals ahead of commencement of work. Landscape Architect requires a minimum of ten (10) working days from date of receipt for review of submittals and response to Owner and Contractor. Plan accordingly for procurement of materials

3. Continuously update implementation schedule and notify Owner of progress. Delays related to material availability are not cause for non-completion of scheduled delivery of work 4. Report delays due to weather or site conditions immediately upon finding. Provide recommendation for

remedy of schedule delays. Do not work, place or modify frozen soil 5. Report delays due to extraordinary natural or other conditions beyond control of Contractor

1. Remove trash, debris and work materials from site prior to request for substantial completion. Thoroughly clean surfaces impacted by work including building, parking areas, roadways, sidewalks, signs, lights, site

2. Repair any damage to existing conditions that occurred during execution of work. 3. All clean-up and demobilization procedures shall be performed to satisfaction of the Owner and Landscape

NOTE: GROUNDCOVERS AND PERENNIALS TO BE INSTALLED WITH TRIANGULAR SPACING PLANT SPACING ROW 'D' 'A' 8" O.C. 6.93" O.C. 'A' 10" O.C. 8.66" O.C. 12" O.C. 10.4" O.C. 18" O.C. 15.6" O.C. 24" O.C. 20.8" O.C. 36" O.C. 30.0" O.C. 48" O.C. 31.5" O.C. **GROUNDCOVER SPACING** XX

GROUNDCOVER PLANTING

NOT TO SCALE


XX

XX

SET GROUNDCOVERS AND PERENNIALS IN STAGGERED ROWS AT SPECIFIED SPACING. MULCH ENTIRE BED WITH 2" SHREDDED HARDWOOD MULCH OR APPROVED EQUAL. MAKE (3) - 1" CUTS IN SIDES OF THE ROOTBALL

EXCAVATE ENTIRE BED AND PLACE PLANTING SOIL MIX PER PLANTING **SPECIFICATIONS**

PLANTING SOIL MIX - SEE SPECS



K WIDTH OF ROOT BALL

SHRUB PLANTING

NOT TO SCALE


SET SHRUB AT ORIGINAL GRADE OR UP TO 1/8 DEPTH OF ROOT BALL 2" SHREDDED HARDWOOD MULCH OR APPROVED EQUAL

MAKE (3) - 1" CUTS IN SIDES OF THE ROOTBALL

PLANTING SOIL MIX PER PLANTING SPECIFICATIONS

UNDISTURBED SOIL PEDESTAL

NOTE: SHRUBS INSTALLED IN CONTINUOUS SUCCESSION OR LARGE BED SHALL BE PLACED IN ONE CONTINUOUS DEPTH BED




SET TREE AT ORIGINAL GRADE OR UP TO 1/8 DEPTH OF ROOT BALL


— 2" SHREDDED HARDWOOD MULCH OR APPROVED EQUAL SOIL SAUCER: USE PREPARED TOPSOIL, 6" MIN.


ROPES AT TOP OF BALL SHALL BE CUT. REMOVE TOP 1/2 OF BURLAP. NON-BIODEGRADABLE MATERIAL SHALL BE TOTALLY REMOVED


PLANTING SOIL MIX PER PLANTING SPECIFICATIONS UNDISTURBED SOIL PEDESTAL











NOT TO SCALE